STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

WALLINGFORD
SNTH 140

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 0.010 LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						X		X												REMOVE EXISTING LEGAL LOAD LIMIT SIGN AND POST LOCATED 312' WEST OF AND ACROSS FROM POLE # VTEL/2/CVP2			
WB	MM 0.010 LT	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		12.25 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 312' WEST OF AND ACROSS FROM POLE # VTEL/2/CVP2	X		
EB	MM 0.013 RT	A B	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00					3			1		11.75 ~~15~~								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 296' WEST OF POLE # VTEL/2/CVP2	X		
EB	MM 0.015 RT	D	R1-1	30	30		STOP	6.25					X		X	1		12.25 ~~15~~								REPLACE THE EXISTING STOP SIGN AND POST LOCATED 285' WEST OF POLE # VTEL/2/CVP2	X		
EB	MM 0.018 RT	A B	D3-1	42	12		West Hill Rd	3.50					1			1		12.75 ~~15~~								INSTALL A NEW STREET NAME SIGN AND POST LOCATED 269' WEST OF POLE # VTEL/2/CVP2		15	
EB	MM 0.018 RT	D	R1-1	30	30		STOP	6.25																		INSTALL A NEW STOP SIGN BENEATH AND ON THE SAME POST AS THE NEW D3-1 SIGN LOCATED 269' WEST OF POLE # VTEL/2/CVP2	X		
EB	MM 0.026 RT	A	W1-6L	48	24								X		X											REMOVE THE EXISTING LARGE LEFT ARROW SIGN AND POST LOCATED 227' WEST OF POLE # VTEL/2/CVP2			
EB	MM 0.026 RT	A	OM1-1	18	18								X													REMOVE EXISTING OBJECT MARKER SIGN LOCATED 227' WEST OF POLE # VTEL/2/CVP2			
EB	MM 0.039 RT	A B	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								1		12.25 ~~15~~								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 158' WEST OF POLE # VTEL/2/CVP2	X		
EB	MM 0.069 RT	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		13.5 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED ADJACENT TO POLE # VTEL/2/CVP2	X		
EB	MM 0.096 RT	A	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 74' WEST OF POLE # CVP3/CTC/3			
EB	MM 0.227 RT	A	W1-2R	30	30								X		X											REMOVE EXISTING CURVE RIGHT SIGN AND POST LOCATED 137' WEST OF MAILBOX # 2172			
										EA	EA	EA	EA ~~6~~ 10	EA	EA 5		FT	FT ~~90~~ 74.75	FT					LB	LB	LB	LB				
								SF 38.00	SF	EA ~~6~~ 10				EA 5		EA 6	FT ~~90~~ 74.75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
WALLINGFORD TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 64 OF 87