

TRAFFIC SIGN SUMMARY SHEET

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST	NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL O/(in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE			RETAIN	REMOVE	FOUNDATION	lb/ft						DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																			1.75	2.00	2.50	3.00					
WB	MM 0.713 LT	F	VW-054	30	30					X				X									RETAIN EXISTING HIDDEN DRIVE RIGHT SIGN AND POST LOCATED 993' EAST OF THE INTERSECTION OF MOONEY ROAD AND ROUTE 140				
WB	MM 0.754 LT	F	WI-1R	30	30					X				X									RETAIN EXISTING RIGHT TURN SIGN AND POST LOCATED 1162' WEST OF AND ACROSS FROM POLE # 12/12				
WB	MM 0.754 LT	F	WI3-1P	18	18					X				X									RETAIN EXISTING ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE EXISTING WI-1R SIGN LOCATED 1162' WEST OF AND ACROSS FROM POLE # 12/12				
WB	MM 0.833 LT	F	VW-054	30	30					X				X									RETAIN EXISTING HIDDEN DRIVE RIGHT SIGN AND POST LOCATED 745' WEST OF AND ACROSS FROM POLE # 12/12				
EB	MM 0.967 RT	A	R8-3	24	24									X	X								REMOVE EXISTING NO PARKING SIGN AND POST LOCATED 37' WEST OF POLE # 12/12				
WB	MM 1.045 LT	F	VW-054	30	30			6.25						X	X	I	14.5 +5						REPLACE THE EXISTING HIDDEN DRIVE RIGHT SIGN AND POST LOCATED ACROSS FROM POLE # 11X/11XX		12		
EB	MM 1.219 RT	A	R2-1	24	30			5.00						X	X	I	13.75 +5						REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 63' WEST OF POLE # 11X/11XX	X			
EB	MM 1.473 RT	A	W7-1A	30	30			6.25						X	X	I	14.5 +5						REPLACE EXISTING HILL SYMBOL SIGN ON ONE NEW POST WITH A HILL SYMBOL SIGN INDICATING 8% GRADE LOCATED 69' EAST OF POLE # 10XX/10XX	X			
EB	MM 1.473 RT	A	WI3-1P	18	18									X									REMOVE EXISTING ADVISORY SPEED PLAQUE LOCATED 69' EAST OF POLE # 10XX/10XX				
EB	MM 1.661 RT	A	WI-2R	30	30																		REMOVE EXISTING CURVE RIGHT SIGN AND POST LOCATED 269' WEST OF AND ACROSS FROM POLE # VTEL/213/9				
EB	MM 1.697 RT	A	WI-2R	30	30			6.25								I	14.0 +5						INSTALL A NEW CURVE RIGHT SIGN AND POST LOCATED 79' WEST OF AND ACROSS FROM POLE # VTEL/213/9	X			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

EA	EA	EA	EA	EA	EA	FT	FT	FT	LB	LB	LB	LB
4				6	4	60	60	60				
				7	5	56.75	56.75	56.75				
					9							
					4							

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)
FILE NAME: 13k036wrk.dgn PLOT DATE: 12/20/2013
PROJECT LEADER: P. COBURN DRAWN BY: N. PATTIS
DESIGNED BY: N. PATTIS CHECKED BY: B. GROSE
WALLINGFORD TRAFFIC SIGN SUMMARY SHEET 3 SHEET 66 OF 87