

TRAFFIC SIGN SUMMARY SHEET

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST	NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL 0/(in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE			RETAIN	REMOVE	FOUNDAION	lb/ft						DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																			1.75	2.00	2.50	3.00					
EB	MM 2.060 RT	A	R2-1	24	30			5.00					X	X	I		13.75						REPLACE THE EXISTING SPEED LIMIT SIGN AND POST LOCATED 211' EAST OF POLE # 93/3/3	X			
WB	MM 2.060 LT	F	R2-1	24	30			5.00					X	X	I		14.75						REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 211' EAST OF AND ACROSS FROM POLE # 93/3/3	X			
WB	MM 2.077 LT - MM 2.143 LT	E F		6 6	8 8		(16) TYPE 11 6"X 8" WHITE DELINEATORS																INSTALL NEW DELINEATORS (16) BACK-TO-BACK SPACED AT 50 FEET APART ON 8 POSTS. INSTALL FIRST 301' EAST OF AND ACROSS FROM POLE # 93/3/3		4		
EB	MM 2.126 RT	A	W11-2	36	36								X		X								RETAIN THE EXISTING PEDESTRIAN SYMBOL SIGN AND POST LOCATED 111' WEST OF AND ACROSS FROM POLE # 921/3/21A/6				
EB	MM 2.126 RT	A	W16-9P	24	12								X		X								RETAIN THE EXISTING AHEAD SIGN AND POST LOCATED 111' WEST OF AND ACROSS FROM POLE # 921/3/21A/6				
EB	MM 2.155 RT	D	R1-1	30	30			6.25							X	X	I						REPLACE THE EXISTING STOP SIGN AND POST LOCATED 42' EAST OF AND ACROSS FROM POLE # 921/3/21A/6	X			
EB	MM 2.155 RT	A	W11-2	36	36								X		X								RETAIN EXISTING SCHOOL SYMBOL SIGN AND POST LOCATED 42' EAST OF AND ACROSS FROM POLE # 921/3/21A/6				
EB	MM 2.155 RT	A	W16-7P	24	12								X		X								RETAIN EXISTING ARROW PLAQUE LOCATED 42' EAST OF AND ACROSS FROM POLE # 921/3/21A/6				
WB	MM 2.155 LT	F	W11-2	36	36								X		X								RETAIN EXISTING SCHOOL SYMBOL SIGN AND POST LOCATED 42' EAST OF POLE # 921/3/21A/6				
WB	MM 2.155 LT	F	W16-7P	24	12								X		X								RETAIN EXISTING ARROW PLAQUE LOCATED 42' EAST OF POLE # 921/3/21A/6				
EB	MM 2.169 RT	A	W10-1	36	36			7.07							X	X	I						REPLACE EXISTING RAILROAD CROSSING SIGN AND POST LOCATED 116' EAST OF AND ACROSS FROM POLE # 921/3/21A/6	X			
EB	MM 2.169 RT	A	OM3-R	12	36			3.00									I						INSTALL A NEW OBJECT MARKER RIGHT SIGN AND POST LOCATED 132' EAST OF AND ACROSS FROM POLE # 921/3/21A/6				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

EA	EA	EA	EA	EA	EA	FT	FT	FT	LB	LB	LB	LB
6			4	6	4	75	66.75					
SF	SF	EA	EA	EA	EA	FT		EA		LB		
26.32		10	11	5		75	66.75					

PROJECT NAME: STATEWIDE SOUTHWEST REGION
 PROJECT NUMBER: STP HRRR(19)
 FILE NAME: 13k036wrk.dgn PLOT DATE: 12/20/2013
 PROJECT LEADER: P. COBURN DRAWN BY: N. PATTIS
 DESIGNED BY: N. PATTIS CHECKED BY: B. GROSE
 WALLINGFORD TRAFFIC SIGN SUMMARY SHEET 5 SHEET 68 OF 87