STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

WHITING
SHOREHAM-WHITING ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS ''A''	NEW SIGNS ''B''	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							SHOREHAM WHITING ROAD																						
EB	MM 0.000 RT	C	VD-024	72	10		Whiting Shoreham	5.00					X		X	2		27.0 ~~30~~								REPLACE EXISTING TOWN LINE SIGN ONE TWO NEW POSTS LOCATED ACROSS FROM POLE # 98		16	
EB	MM 0.002 RT	A	R2-1	24	30		SPEED LIMIT 50	5.00								1		15.5 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 11' EAST OF AND ACROSS FROM POLE # 98	X		
WB	MM 0.002 LT	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		13.5 ~~15~~								INSTALL A SPEED LIMIT SIGN AND POST LOCATED 11' EAST OF POLE # 98	X		
EB	MM 0.211 RT	A	W1-2L	30	30			6.25								1		15								INSTALL NEW CURVE LEFT SIGN AND POST LOCATED 121' WEST OF AND ACROSS FROM POLE # 92	X		
EB	MM 0.211 RT	A	W13-1P	18	18		40 MPH	2.25																		INSTALL NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-2L SIGN LOCATED 121' WEST OF AND ACROSS FROM POLE # 92	X		
EB	MM 0.258 RT	A B	W1-8R W1-8L	18 18	24 24		B-B	3.00 3.00								1		13.0 ~~15~~								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 127' EAST OF AND ACROSS FROM POLE # 92	X		
EB	MM 0.280 RT	B	W1-8L	18	24								X		X											REMOVE EXISTING LEFT CHEVRON SIGN AND POST LOCATED 37' EAST OF POLE # 91			
EB	MM 0.282 RT	B	W1-8L	18	24								X		X											REMOVE EXISTING LEFT CHEVRON SIGN AND POST LOCATED 48' EAST OF POLE # 91			
EB	MM 0.288 RT	A B	W1-8R W1-8L	18 18	24 24		B-B	3.00 3.00								1		13.25 ~~15~~								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 79' EAST OF POLE # 91	X		
EB	MM 0.290 RT	A	W1-8	18	24								X		X											REMOVE EXISTING RIGHT CHEVRON SIGN AND POST LOCATED 90' EAST OF POLE # 91			
EB	MM 0.293 RT	A	W1-8	18	24								X		X											REMOVE EXISTING RIGHT CHEVRON SIGN AND POST LOCATED 106' EAST OF POLE # 91			
EB	MM 0.319 RT	A B	W1-8R W1-8L	18 18	24 24		B-B	3.00 3.00								1		12.25 ~~15~~								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT ACROSS FROM POLE # 8/90	X		
WB	MM 0.350 LT	F	W1-2R	30	30			6.25								1		15.25 ~~15~~								INSTALL A NEW CURVE RIGHT SIGN AND POST LOCATED 164' EAST OF POLE # 8/90	X		
WB	MM 0.350 LT	F	W13-1P	18	18		40 MPH	2.25																		INSTALL A NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-2R SIGN LOCATED 164' EAST OF POLE # 8/90	X		
										EA	EA	EA	EA 5	EA	EA 5		FT	FT ~~135~~ 124.75	FT		LB	LB	LB	LB					
								SF 50.00	SF	EA 5				EA 5		EA 9	FT ~~135~~ 124.75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
WHITING TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 75 **OF** 87