STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

WHITING
LEICESTER-WHITING ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS ''A''	NEW SIGNS ''B''	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O (in) FOUNDATION	TUBULAR STEEL O (in) 3.00 lb/ft 7.60	TUBULAR STEEL O (in) 3.50 lb/ft 9.00	TUBULAR STEEL O (in) 4.00 lb/ft 10.80	TUBULAR STEEL O (in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 2.201 RT	A	WI-2L	30	30			6.25								1		13.75 ~~15~~									INSTALL A NEW CURVE LEFT SIGN AND POST LOCATED ACROSS FROM POLE # 8/11	X		
EB	MM 2.241 RT	A B	WI-8L WI-8R	18 18	24 24			3.00 3.00								1		13.0 ~~15~~									INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 58' WEST OF AND ACROSS FROM POLE # 16	X		
EB	MM 2.254 RT	B	WI-8R	18	24								X		X												REMOVE EXISTING CHEVRON AND POST LOCATED 11' EAST OF AND ACROSS FROM POLE # 16			
EB	MM 2.256 RT	B	WI-8R	18	24								X		X												REMOVE EXISTING CHEVRON AND POST LOCATED 21' EAST OF AND ACROSS FROM POLE # 16			
WB	MM 2.262 RT	A	WI-8L	18	24								X		X												REMOVE EXISTING CHEVRON AND POST LOCATED 53' EAST OF AND ACROSS FROM POLE # 16			
EB	MM 2.263 RT	A B	WI-8L WI-8R	18 18	24 24			3.00 3.00								1		12.25 ~~15~~									INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 58' WEST OF AND ACROSS FROM POLE # 16	X		
EB	MM 2.264 RT	A	WI-8L	18	24								X		X												REMOVE EXISTING CHEVRON AND POST LOCATED 63' EAST OF AND ACROSS FROM POLE # 16			
EB	MM 2.283 RT	A	R2-5	24	30								X		X												REMOVE EXISTING REDUCED SPEED AHEAD SIGN AND POST LOCATED 37' WEST OF POLE # 9			
EB	MM 2.286 RT	A B	WI-8L WI-8R	18 18	24 24			3.00 3.00								1		12.0 ~~15~~									INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 21' WEST OF POLE # 9	X		
EB	MM 2.290 RT	A	W3-5	36	36			9.00								2		27.75 ~~30~~									INSTALL A NEW SPEED LIMIT 35 MPH AHEAD SIGN ON TWO POSTS LOCATED ADJACENT TO POLE # 9	X		
EB	MM 2.334 LT	F	WI-2R	30	30			6.25								1		12.75 ~~15~~									INSTALL A NEW CURVE RIGHT SIGN AND POST LOCATED 21' EAST OF AND ACROSS FROM POLE # 8	X		
EB	MM 2.365 RT	A	R2-1	24	30			5.00								1		14.5 ~~15~~									INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 185' EAST OF POLE # 8	X		
WB	MM 2.365 LT	F	WI-2	30	30								X		X												REMOVE EXISTING CURVE RIGHT SIGN AND POST LOCATED 185' EAST OF AND ACROSS FROM POLE # 8			
										EA	EA	EA	EA 6	EA	EA 6		FT	FT ~~120~~ 106.0	FT		LB	LB	LB	LB					
								SF 44.50	SF	EA 6				EA 6		EA 8	FT ~~120~~ 106.0			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
WHITING TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 80 **OF** 87