STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

WHITING
WEST ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
WB	MM 2.365 LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		13.0 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 185' EAST OF AND ACROSS FROM POLE # 8	X		
WB	MM 2.366 LT	G	VD-024	72	10		Whiting | Leicester	5.00					X		X	2		22.5 ~~30~~								REPLACE EXISTING TOWN LINE SIGN ON TWO NEW POSTS LOCATED 190' EAST OF AND ACROSS FROM POLE #8		16	
							WEST ROAD																						
SB	MM 0.007 RT	A	VR-017	24	30		~~LEGAL LOAD LIMIT 24,000 POUNDS~~ SPEED LIMIT 35						X		X											REMOVE EXISTING LEGAL LOAD SIGN AND POST LOCATED 37' SOUTH OF THE INTERSECTION OF WEST ROAD AND SHOREHAM WHITING ROAD			
SB	MM 0.007 RT	C D	D3-1	30	12		West Rd	2.50					X		X	1		15								REPLACE EXISTING STREET NAME SIGN AND POST LOCATED 37' SOUTH OF THE INTERSECTION OF WEST ROAD AND SHOREHAM WHITING ROAD		15	
SB	MM 0.007 RT	B	R1-1	30	30		STOP	6.25					X													REPLACE EXISTING STOP SIGN AND INSTALL IT BENEATH THE NEW D3-1 SIGN LOCATED 37' SOUTH OF THE INTERSECTION OF WEST ROAD AND SHOREHAM WHITING ROAD	X		
NB	MM 0.016 LT	F	R1-1	30	30		STOP	6.25					~~2~~ X		X	1		13.25 ~~15~~								REPLACE EXISTING STOP SIGN AND POST LOCATED 169' NORTH OF POLE # 40T/8/85	X		
NB	MM 0.080 LT	F	W3-1	30	30			6.25								1		14.0 ~~15~~								INSTALL A NEW STOP AHEAD SIGN AND POST LOCATED 169' SOUTH OF POLE # 40T/8/85	X		
							CROSBY ROAD																						
SB	MM 0.011 LT	E	W14-1	30	30		DEAD END						X		X											REMOVE EXISTING DEAD END SIGN AND POST LOCATED 5' NORTH OF AND ACROSS FROM POLE # 46			
SB	MM 0.011 LT	H G	D3-1	36	12		Crosby Rd	3.00					X		X	1		13.5 ~~15~~								REPLACE EXISTING STREET NAME SIGN AND POST LOCATED 5' NORTH OF AND ACROSS FROM POLE # 46		13	
SB	MM 0.011 LT	F	R1-2	36	36		YIELD	4.50					X													REPLACE EXISTING YIELD SIGN BENEATH AND ON THE SAME POST AS THE NEW D3-1 SIGN LOCATED 5' NORTH OF AND ACROSS FROM POLE # 46	X		
NB	MM 0.015 RT	A	W14-2	30	30		NO OUTLET	6.25								1		14.0 ~~15~~								INSTALL A NEW NO OUTLET SIGN AND POST LOCATED 26' NORTH OF POLE # 46	X		
										EA	EA	EA	EA ~~8~~ 9	EA	EA 6		FT	FT ~~120~~ 105.25	FT			LB	LB	LB	LB					
								SF 45.00	SF	EA ~~8~~ 9				EA 6		EA 8		FT ~~120~~ 105.25		EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
WHITING TRAFFIC SIGN SUMMARY SHEET 7

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 81 **OF** 87