

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									4		4		CY	STRUCTURE EXCAVATION	204.25				
									4		4		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
									13		13		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
									1		1		LS	SHORING SUPERSTRUCTURE	502.10				
									760		760		LB	STRUCTURAL STEEL	506.60				
									830		830		LB	REINFORCING STEEL, LEVEL I	507.11				
									16		16		LF	DRILLING AND GROUTING DOWELS	507.16				
									2		2		GAL	WATER REPELLENT, SILANE	514.10				
									4.8		4.8		MFBM	STRUCTURAL LUMBER AND TIMBER, UNTREATED	522.20				
									0.7		0.7		MFBM	STRUCTURAL LUMBER AND TIMBER, TREATED	522.25				
									2		2		MFBM	NONSTRUCTURAL LUMBER, UNTREATED	522.30				
									1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (2.1 MFBM)(FLOORBEAMS)	522.40				
									1		1		LS	STRUCTURAL GLUED LAMINATED TIMBER (5.4 MFBM)(DECK)	522.40				
									20		20		LF	BRIDGE RAILING REPAIR, TYPE III	525.60				
									1		1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
									8		8		CY	REMOVAL OF CONCRETE OR MASONRY	529.25				
									10		10		SY	REPAIRING STONE MASONRY	602.40				
								45			45		LF	REMOVE AND RESET GUARDRAIL	621.75				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
									1		1		LS	MOBILIZATION/DEMobilIZATION	635.11				
									1		1		LS	TRAFFIC CONTROL	641.10				
									1		1		LS	TIMBER PAINTING, ENVIRONMENTAL PROTECTION	660.10				
									1		1		LS	TIMBER PAINTING, FIRE RETARDANT	660.20				
									1		1		LS	TIMBER PAINTING, INSECTICIDE/FUNGICIDE	660.30				
								10			10		SF	TRAFFIC SIGNS, TYPE A	675.20				
								2			2		EACH	REMOVING SIGNS	675.50				
									1		1		LS	SPECIAL PROVISION (REHABILITATING COVERED BRIDGE SUPERSTRUCTURE)	900.645				