



* INTSALL SIGNS ON TYPE III BARRICADES.

EACH	SIGN DIMENSIONS		2 IN SQ X 10 FT STEEL POST	MUTCD SIGN NUMBER / STD NUMBER
	WIDTH (in)	HEIGHT (in)		
2	60	30	-	R11-4 (ROAD CLOSED TO THRU TRAFFIC)
1	48	18	-	M4-10L (DETOUR ARROW LEFT)
2	48	48	2	VC-869 (SIDE ROAD WORK AHEAD) (SEE STD T-28)
3	48	48	2	W20-2 (DETOUR AHEAD)
16	42	12	-	D3 (ROSCOE RD)
3	30	24	1	M4-9L (DETOUR LEFT ARROW)
4	30	24	1	M4-9R (DETOUR RIGHT ARROW)
9	30	24	1	M4-9 (DETOUR VERTICAL ARROW)
2	24	18	1	M4-8a (END DETOUR)
1	60	30	2	R11-3b (BRIDGE OUT/1 MILE AHEAD/LOCAL TRAFFIC ONLY)
1	60	30	2	R11-3b (BRIDGE OUT/2 MILES AHEAD/LOCAL TRAFFIC ONLY)
1	60	30	2	R11-3b (BRIDGE OUT/ROSCOE ROAD/FOLLOW DETOUR)
			EA	
			14	
SQ FT			FT	
291			140	

DETOUR SIGNING WILL BE THE RESPONSIBILITY OF THE TOWN. PROPOSED DETOUR ROUTE AND SIGNAGE SHOWN IS NOT INCLUDED IN THE CONTRACT. USE FOR TOWN REFERENCE ONLY.

PROJECT NAME: CHARLOTTE
 PROJECT NUMBER: BO 1445(36)
 FILE NAME: sl4j235detour.dgn
 PROJECT LEADER: M. SARGENT
 DESIGNED BY: G. ROY
 DETOUR LAYOUT
 PLOT DATE: 26-FEB-2016
 DRAWN BY: G. ROY
 CHECKED BY: J. WEAVER
 SHEET 12 OF 13