

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS			DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
							ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
							1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-				
							6930			6930		CY	COMMON EXCAVATION	203.15	91.6				
							1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST				
							20			20		HR	POWER BROOM RENTAL, TYPE II	608.31	EST				
							20			20		HR	TRUCK RENTAL	608.37	EST				
							120			120		MGAL	DUST CONTROL WITH WATER	609.10	2.5				
							1200			1200		CY	STONE FILL, TYPE II	613.11	41.3				
							2			2		EACH	YIELDING MARKER POSTS	619.17	-				
							130			130		LF	CHAIN-LINK FENCE, 6 FEET	620.12	-				
							3			3		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	-				
							80			80		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST				
							440			440		HR	FLAGGERS	630.15	EST				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-				
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-				
							1			1		LS	MOBILIZATION/DEMobilIZATION	635.11	-				
							1			1		LS	TRAFFIC CONTROL	641.10	-				
							2			2		EACH	RAILROAD CROSSING SYMBOL, WATERBORNE PAINT	646.321	-				
							1800			1800		SY	GEOTEXTILE UNDER STONE FILL	649.31	36.9				
								320		320		SY	GEOTEXTILE FOR SILT FENCE	649.51	4				
								80		80		LB	SEED	651.15	6.6				
								620		620		LB	FERTILIZER	651.18	8.4				
								1.5		1.5		TON	AGRICULTURAL LIMESTONE	651.20	0.3				
								1.5		1.5		TON	HAY MULCH	651.25	0.3				
							175			175		CY	TOPSOIL	651.35	11.3				
							1500			1500		SY	GRUBBING MATERIAL	651.40	12.7				
								1		1		LS	EPSC PLAN	652.10	-				
								100		100		HR	MONITORING EPSC PLAN	652.20	EST				
								1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-				
								1700		1700		SY	TEMPORARY EROSION MATTING	653.20					
								5		5		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	2.7				
								50		50		CY	VEHICLE TRACKING PAD	653.35	5.6				
								1		1		EACH	INLET PROTECTION DEVICE, TYPE II	653.41	-				
								560		560		LF	PROJECT DEMARCATION FENCE	653.55	9.4				
							55			55		SF	TRAFFIC SIGNS, TYPE A	675.20	1.2				
							140			140		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-				
							5			5		EACH	REMOVING SIGNS	675.50	-				
							1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-				
							1			1		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-				
							1			1		LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N.A.B.I.)	900.650	-				
							100			100		SY	SPECIAL PROVISION (RETAINING WALL)	900.675	1.1				

The following product(s) are not activated:

ProjectWise InterPlot Script

PROJECT NAME:	BARRE CITY - BARRE TOWN	FILE NAME:	z15d040quantity.dgn	PLOT DATE:	12/5/2016
PROJECT NUMBER:	MEGC M 6000(II)C/1	PROJECT LEADER:	A.P. GUYETTE	DRAWN BY:	P.A. MILLER
		DESIGNED BY:	P.A. MILLER	CHECKED BY:	D.M. PECK
		QUANTITY SHEET		SHEET	II OF 39

