

The following product(s) are not activated:

Projectwise InterPlot Server

MEMO TO: Bryan Sicard – Redi-Rock Walls of New England

This memo forwarded by e-mail only unless otherwise requested

FROM: Eric Merluzzi, P.E.
184 Rowentown Road
Wentworth, NH 03282
Phone: (603) 786-2751
e-mail: em35@earthlink.net

SUBJECT: Wall Quantities
Quarry Street
Barre, VT
Job No. 2017-001
Plan Date: 12/2/16, No Revisions

DATE: February 27, 2017

Wall #1:

Wall Area: 983 SF
Wall Length: 111 LF

Geogrid: Miragrid 5XT – 950 SY

Block Count:

½ Garden Corner – 12
Top – 23
½ 28" Middle - 1
28" Middle – 114
28" Bottom – 27
Fiberglass Connection Rods - 142