



**NOTES:**

1. PRECAST CONCRETE BLOCKS SHALL BE OF THE DIMENSIONS SHOWN WITH A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.
2. ANCHOR RODS SHALL CONFORM TO ASTM F1554, GRADE 36.
3. HOLES FOR ANCHOR RODS SHALL BE DRILLED TO A MINIMUM OF 1" LARGER DIAMETER THAN THE ROD AND SET WITH MORTAR, TYPE IV.

PROJECT NAME: MIDDLEBURY	PLOT DATE: 5/19/2017
PROJECT NUMBER: EWP3(1)	DRAWN BY: R.H. BARNES
FILE NAME: z17b016_TYP_PedBridge.dgn	CHECKED BY: E.P. DETRICK
DESIGNED BY: R.H. BARNES	PED. BRIDGE & WATERLINE ABUTMENT DETAILS SHEET 9 OF 54

