STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (IN)	HEIGHT (IN)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL LB/FT 1.12	2.0	3.0	SQUARE STEEL (IN) LB/FT 1.88	1.75 2.0	2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) LB/FT 1.3	3.0	4.0	4.0 MOD 1.7	1.7	WOOD POST (LF) COLLAR	TYPE 1	TYPE 2	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
OPTION ITEMS																																			
MAIN STREET																																			
9+44, LT		1	24	24	4.00						1					X		X															SHSM R3-2		
10+04, LT	RESERVED PARKING						1				1					X		X															EXISTING SIGN REMOVE AND SALVAGE ON NEW POST FROM STA 11+05, LT		
12+75, RT	RESERVED PARKING						1				1					X		X															EXISTING SIGN REMOVE AND SALVAGE ON NEW POST FROM STA 11+63, RT		
MERCHANTS ROW																																			
20+40, LT	MERCHANTS ROW						1																											EXISTING SIGN REMOVE AND SALVAGE ON NEW POST FROM STA 20+49, LT		
20+40, LT	MAIN ST						1																											EXISTING SIGN REMOVE AND SALVAGE ON NEW POST FROM STA 20+49, LT		
20+40, LT	STOP						1				1					X		X															EXISTING SIGN REMOVE AND SALVAGE ON NEW POST FROM STA 20+49, LT		
20+40, LT		1	24	24	4.00																												SHSM R3-2 MOUNT BELOW SALVAGED R1-1		
20+40, LT	0300 0111 0168						1																											EXISTING SIGN REMOVE AND SALVAGE ON NEW POST FROM STA 20+49, LT		
20+55, LT	NO PARKING LOADING ZONE →	1	12	18	1.50						1					X		X															SHSM R7-6R		
21+08, LT	NO PARKING LOADING ZONE ←	1	12	18	1.50						1					X		X															SHSM R7-6L		
21+31, RT	← ONE WAY	1	36	12	3.00																												SHSM R6-1L MOUNT ABOVE R4-8		
21+31, RT	ONE WAY →	1	36	12	3.00																												SHSM R6-1R MOUNT BACK TO BACK WITH R6-1L		
21+31, RT		1	24	30	5.00						1					X		X															SHSM R4-8		
21+36, LT	ONE WAY →	1	36	12	3.00						1					X		X															SHSM R6-1R		
												FT	FT	FT	FT	FT 120	FT	EA	LB	LB	LB		TYPE 1	TYPE 2									
TOTALS					SF 25.00	SF	EA. 6	SF				FT			FT 120				LB			EA.	WOOD POSTS (FT)		EA.	EA.	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

WOG = WHITE LEGEND ON GREEN BACKGROUND - PLAQUE
FYG = BLACK LEGEND ON FLUORESCENT YELLOW-GREEN BACKGROUND
SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK (WITH 2012 SUPPLEMENT)

POST LENGTH AVERAGES 15 FEET

POST LENGTH WITH '+' AVERAGES 20 FEET

vhb

PROJECT NAME: MIDDLEBURY
PROJECT NUMBER: EWP3(1)

FILE NAME: z17b016_TSSS.dgn
PROJECT LEADER: A.P. GUYETTE
DESIGNED BY: D.M. PECK
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 5/19/2017
DRAWN BY: D.M. PECK
CHECKED BY: E.P. DETRICK
SHEET 26 OF 54

VHB 57603.00