



- NOTES:**
1. PRECAST CONCRETE BLOCKS SHALL BE OF THE DIMENSIONS SHOWN WITH A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSL
 2. ANCHOR RODS SHALL CONFORM TO ASTM F1554, GRADE 36.
 3. HOLES FOR ANCHOR RODS SHALL BE DRILLED TO A MINIMUM OF 1" LARGER DIAMETER THAN THE ROD AND SET WITH MORTAR, TYPE IV.



REVISIONS			KUBRICKY CONSTRUCTION		
NO.	DATE	BY	CONTRACT No. EWPS(1)		
1			MIDDLEBURY		
2			PEDESTRIAN BRIDGE SHOP DRAWINGS		
3			DESIGNED	DATE	DRAWING NO.
4			CHECKED	DATE	PB-02
5					

7/11/2017 9:07:55 AM