



The dimension from centerline pedestrian bridge to centerline girder should be 1'-9" (TYP) as shown in other details in this set.

A 5/8" threaded rod is acceptable for use here instead of hex head bolt. It should be ASTM A449 with split lock washers at both ends.

16d(3 1/2") is an acceptable substitute the 20d(4") nails.

INDICATES NAILS IN FIRST LAMINATION
+ INDICATES NAILS IN SECOND LAMINATION
x INDICATES NAILS IN THIRD LAMINATION