



ESTIMATE OF QUANTITIES		
ITEM	DESCRIPTION	QUANTITY
429C	#1 GAL. CORR. GALV. METAL PLATE PIPE ARCH (2)	6640 LBS
401C	CONCRETE CLASS "C"	24 C.Y.
107	STRUCTURE EXCAVATION (MOD)	95 C.Y.
110	CUTTING & REMOVING TREES	3 EA
411	CEMENT RUBBLE MASONRY	142 C.Y.
574	PREPARING SUPERSTRUCTURE FOR WIDENING	1 L.S.
222	GRAVEL BACKFILL	36 C.Y.
402	REINFORCING STEEL	366 LB
542	TWO CABLE GUARD RAIL	80 LF
201A	SUB BASE OF GRAVEL - BRIDGE ONLY	26 C.Y.
106-G	UNCLASSIFIED CHANNEL EXCAVATION	9 C.Y.

STATE OF VERMONT
DEPARTMENT OF HIGHWAYS

TOWN OF TOWNSHEND

ROAD No. 1 BRIDGE No. 4

CORR. GALV. METAL PLATE PIPE

ARCH EXT. OF EXISTING STONE ARCH

SCALE 3" = 1'-0"

SURVEYED BY POGAR

DRAWN BY MLJ CHECKED BY B.B.M.

PROJECT No. SA 17-1953

SHEET 3 OF 10