



 = APPROXIMATE LOCATION OF PETROLEUM CONTAMINATED SOIL

CURVE # 1
Δ = 2° 41' 36" LT.
D = 1' 30"
R = 3819.72'
T = 89.79'
L = 179.56'
E = 1.06'
DO NOT BANK

P.O.T. II+54.93 =
RIVER ST. TRAV.
P.I. 80+00.00

BM # 1
ON SE ABUT.
OF BRIDGE
ELEV. 535.78

NET
24
87

NET
344
25
GMP
86

*26
GMP
85
GUY
POLE

GRANITE
STREET
BRIDGE

POLE W/LIGHT
SIGNAL BOX

4" WATER LINE

24" RCP SEWER

S 35° 37' 53" E

S 14° 00' 00" E

S 16° 41' 36" E

1/4" WATER LINE

ABANDONED
SERVICE
FOR STORE

SEWER
DIVERSION

SEWER
DIVERSION

SEWER
DIVERSION

79+00

11+00

12+00

13+00

14+00

15+00

16+00

17+00

18+00

19+00

20+00

21+00

22+00

23+00

24+00

25+00

11+35
OFF 73'

PI 13+90.35
= 13+90.33

15+58
OFF 83'

APPROX. AERIAL
RELOCATION BY
NET, GMP, & FACTV

**ARCHIVED
ON CADD**

NOTE: THE STONE WALL LOCATED @
16+18LT IS TO BE COMPLETELY REMOVED.
THE STONE FROM THIS WALL IS TO BE
RESET FROM 15+45LT 15+95LT (SEE
X-SECTION SHEET I55 AND SPECIAL PROVISIONS)
WORK TO REMOVE AND RESET THE STONE WALL
WILL BE PAID UNDER ITEM 602.20,
DRY RUBBLE MASONRY, AND THE COSTS WILL
BE NON-GOV'T. PARTICIPATION.

0 20 40
SCALE IN FEET

NEW ELBOW 12" W/ T4VCSF .064
OR C&P 1060 W/2 ELBOWS @ 85 & 25

DATUM
VERTICAL NGVD 1929
HORIZONTAL N/A

SURVEYED BY MOREAU DATE 7-85
DRAWN BY COTA/NAILOR DATE 4-88
SQUAD LEADER SHERIDAN
DESIGN FILE NO. /usr/const/76b033/cb033a
PRF FILE cb033csl DATE PLOTTED 26-FEB-1996
PROJ. NAME MONTPELIER
PROJ. NO. MEGC M 6400(7)
SHEET 61A OF 355 SHEETS