

QUANTITIES

NO.	ITEM	UNIT	ESTIMATE					FINAL							
			Wall #1	Wall #2	Wall #3	Wall #4	Wall #5	TOTAL	Wall #1	Wall #2	Wall #3	Wall #4	Wall #5	TOTAL	
204.25	Structure Excavation	C.Y.	105	295	165	80	135	780							
204.30	Granular Backfill for Structures	C.Y.	65	235	130	85	95	610							
501.25	Concrete (C. B)	C.Y.	25	95	46	32	41	239							
506.60	Structural Steel (anchor bolts)	lb.	253	7				260							
509.19	Epoxy Coated Reinforcing Steel	lb.	2565	9605	5025	3805	4890	25,890							
514.10	Water Repellent	gal.	2	11	5	3	5	26							
525.15	Metal Hand Rail, 1-Rail	l.f.	17	39	28	31	11	126							
625.15	Metal Hand Rail (Mod) 3-Rail	l.f.		167	78	41	81	367							
*631.16	Testing Equipment - Concrete	l.s.						1							
*651.35	Topsoil	C.Y.	3	9	5	2	9	28							
* PAID AS ROADWAY ITEMS															

NOTES

SEE SHEET 2 OF 10 FOR RETAINING WALL NOTES.

STATE OF VERMONT	
AGENCY OF TRANSPORTATION	
Town of <u>MONTPELIER</u>	Plan No. <u> </u>
Highway No. <u>BERLIN STREET</u>	Loc. Sta. <u> </u>
Quantities for new Retaining Walls Along Berlin St.	
Checked By <u>R.E. Provost</u>	Checked By <u>R.M. Walker</u>
Date <u>7/89</u>	Date <u> </u>
By <u>R.P. Gordon</u>	By <u> </u>
Montpelier - Berlin St. <u> </u>	
Scale <u>N/A</u>	
Sheet No. <u>1</u> OF <u>10</u> 103 of 313	