: Sheet Number: 6

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL		UTILITIES NO/FEDERAL/STATE PARTICIPATION	UTILITIES	FULL E.&C.		ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				1			1	LS	FIELD OFFICE-ENGINEERS	631.10	-
				1			1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
				1			1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
				1			1	LU	FIELD OFFICE TELEPHONE (NOT A BID ITEM)	631.25	-
						1	1	LS	MOBILIZATION	635.10	EST.
						35	35	LF	JACKING OR BORING WELDED STEEL PIPE	643.20	-
						2150	2150	LF	DURABLE 4'' YELLOW LINE	646.41	108
						126	126	LF	DURABLE 24'' STOP BAR	646.46	-
						36	36	EA	DURABLE LETTER OR SYMBOL	646.50	-
						6450	6450	LF	TEMPORARY 4'' YELLOW LINE	646.61	36
						42	42	LF	TEMPORARY 24'' STOP BAR	646.66	-
						12	12	EA	TEMPORARY LETTER OR SYMBOL	646.70	-
150							150	SY	GEOTEXTILE FOR SILT FENCE	649.51	EST.
25							25	LB	SEED	651.15	-
25							25	LB	SEED-WINTER RYE	651.17	-
100							100	LB	FERTILIZER	651.18	-
1							1	TON	AGRICULTURAL LIMESTONE	651.20	-
1							1	TON	HAY MULCH	651.25	-
						65	65	CY	TOPSOIL	651.35	-
50							50	SY	EROSION MATTING	654.10	-
						5	5	EA	EVERGREEN SHRUBS	656.25	-
						55	55	EA	DECIDUOUS SHRUBS	656.35	-
						5	5	EA	TRANSPLANTING SHRUBS	656.50	-
						45	45	SF	TRAFFIC SIGNS, TYPE A	675.20	1.37
									''BEGIN OPTION ITEM ''		
						230	230	LF	FLANGED CHANNEL SIGN POST W/ANCHOR	675.301	-
						230	230	LF	SQUARE TUBE STEEL SIGN POST	675.341	-
									''END OPTION ITEM ''		
						7	7	EA	REMOVING SIGNS	675.50	-
			1460				1460	LF	ELECTRICAL CONDUIT (3'' PVC)	678.21	
			120				120	LF	ELECTRICAL CONDUIT (3'' STEEL)	678.21	
			6930				6930	LF	ELECTRICAL CONDUIT (4'' PVC)	678.21	
			111				111	LF	ELECTRICAL CONDUIT (4'' STEEL)	678.21	
		1090	1270			720	3080	LF	WIRED CONDUIT	678.23	
			1				1	EA	PULL BOX STANDARD	678.25	EST
			1				1	EA	JUCTION BOX	678.26	EST
						4	4	EA	LUMINAIRE	679.50	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

SURVEYED BY _____ DATE _____
DRAWN BY A. JONES DATE 7/94
SQUAD LEADER S. MENARD
DESIGN FILE NO. /usr/84d714/dd714.dgn
IPARM FILE dd714q3 DATE PLOTTED 28-APR-1999
PROJ. NAME OLD BENNINGTON
PROJ. NO. M 1400 (4)S
SHEET 6 OF 63 SHEETS