

INDEX OF SHEETS AND SEEDING INFORMATION

1.	TITLE SHEET	
2.	INDEX OF SHEETS AND SEED INFORMATION	
3.	PROJECT DESCRIPTION AND LOCATION	
4.	TYPICAL SECTIONS AND DESIGN DATA	
5-7.	QUANTITY SHEETS	
8.	UTILITIES LAYOUT SHEET (APPROX. LOCATION)	
9.	PAVEMENT MARKING DETAILS & NOTES	
10.	BLANK	
11.A-66	URBAN TYPICAL SECTIONS	11/21/80 R
12.B-71	STD FOR RES AND COM DRIVES	07/23/80 R
13.C-1	CAST IN PLACE CEMENT CONCRETE CURB	12/16/80 R
14.C-2A	PORTLAND CEM CONCRETE SIDEWALK	12/14/71
15.D-8	REINF CONC DI w/GRATE (BOTTOM SECTION)	12/06/71
16.D-9	REINF CONC DI TOP	12/06/71
17.D-11	CAST IRON GRATE TYPE A	08/24/81 R
18.D-20	HIGHWAY CROSSINGS FOR UNDERGROUND UTILITIES	09/09/75 R
19.	BLANK	
20.E-2	ROAD CONST APPROACH SIGNS	03/04/81 R
21.E-6	ON-PROJECT CONST SIGNS	04/01/80 R
22.E-15C	REGULATORY	07/18/84
23.E-29	STANDARD SIGN PLACEMENT	08/25/81 R
24.E-50	PAVEMENT MARKING DETAILS	03/16/82 R

SEEDING FORMULA ITEM 651.10

URBAN AREAS

<u>%WT. LBS/A</u>	<u>NAME</u>	<u>PUR%</u>	<u>GERM%</u>
37.50 30	CREEPING RED FESCUE (VAR. PENNLAWN)	98	85
31.25 25	KENTUCKY BLUEGRASS (COMMON)	85	75
31.25 25	PERENNIAL RYE GRASS (VAR. PENNLAWN)	95	90
100 80			

FERTILIZER. ITEM 651.15
 FORMULA 10-20-10 TO BE USED WITH SEED.
 ITEM 651.10 APPLIED AT THE RATE OF 500LBS/ACRE

AGRICULTURAL LIMESTONE ITEM 651.20
 TO BE APPLIED AT RATE OF 2 TONS/ACRE
 OR AS DIRECTED BY THE ENGINEER

HAY MULCH ITEM 651.25
 TO BE PLACED ON EARTH SLOPES AT THE RATE
 OF 2 TONS/ACRE

TOPSOIL ITEM 653.10
 TO BE USED WITH SEED. ITEM 651.10 IN
 RESIDENTIAL AREAS, AS DIRECTED BY
 THE ENGINEER

PROJECT St. Albans

NO M8000(11)S
 SHEET 2 OF 24 SHEETS