ITEM QUANTITIES

ITEM DESCRIPTION		Cast Iron Grate w/Frame, Type "A"	All Purpose Excavator Rental, Type I	Truck Rental	Dust Control w/ water	Cast-in-Place Cem. Conc. Curb Type "B"	Portland Cem. Conc. Sidewalk-5 inch	Portland Cem. Conc. Sidewalk-8 inch	Adjust Elev of Valve Box	Uniformed Traffic Officers	Flagpersons	Mobilization	Temporary 4" Reflect. Yellow Lines	Temporary 24" STOP Bar		REMARKS
ITEM NO.		604.45	608.25	608.37	609.10	616.26	618.10	618.11	629.20	630.10	630.15	635.10	646.36	646.77		
UNIT		EA	HR	HR	M/Gal.	LF	SY	SY	EA	HR	HR	LS	LF	LF		
LOCATION																
Project												1				
Project		6	16	16	55	1400	5		7	40	75					Est.
Sidewalk							34	20								(4' wide) See Sheet # 8
Allen St.													1400	34		
Stowell St.														17		
Rounding							1									
Totals		6	16	16	55	1400	40	20	7	40	75	1	1400	51		

PROJECT ST ALBANS NUMBER M 8000 (11) S SHEET 6 OF 24