



DRIVE PILES TO 18 TON CAPACITY. LENGTH 30'-0" FOR ESTIMATING PURPOSES ONLY.

POWNA
BRZ 144(19) C/2
REFERENCE SHEET 4 OF 18
SHEET 94 OF 108

ABUTMENT #2 - DETAILS
VILLAGE BRIDGE
NORTH POWNA

ESTIMATED QUANTITIES

STRUCT. EXCAV.	132 C.Y.	Surveyed by Designed by W.H.D. 5/2/39 Drawn by W.H.D. 5/2/39 Traced by J.W.P. Checked by L.T.A.B. Series 582 No. 18 Filed
CHANNEL EXCAV.	1930 C.Y.	
CONCRETE CLASS "C"	56 C.Y.	
REINFORCING STEEL	373 LBS.	
TIMBER PILING	660 L.F.	
STONE FILL	445 C.Y.	