



MARK	QTY	"a"	"b"	"c"	"d"	"e"	"f"	"g"	"h"	"i"	"j"	"k"	"l"	"m"	"n"	PANEL ASSY.
BP3	1	7'-2 7/8"	4 15/16"	11	6'-5"	4 15/16"	2'-0 11/16"	2'-2 7/16"	2"	6 7/16"	1'-9"	1'-9"	6 7/16"	2"		PANEL ASSY.
BP4	1	7'-2 7/8"	4 15/16"	11	6'-5"	4 15/16"	2'-1"	2'-2 1/8"	2"	6 7/16"	1'-9 1/2"	1'-8 1/2"	6 7/16"	2"		BP3
BP5	1	7'-2 7/8"	4 15/16"	11	6'-5"	4 15/16"	2'-1 5/8"	2'-1 1/2"	2"	6 7/16"	1'-9 1/2"	1'-8 1/2"	6 7/16"	2"		BP4
BP6	1	7'-2 7/8"	4 15/16"	11	6'-5"	4 15/16"	2'-2 1/16"	2'-1 1/16"	2"	6 7/16"	1'-10"	1'-8"	6 7/16"	2"		BP5
BP8	1	7'-3"	5"	11	6'-5"	5"	2'-2 1/4"	2'-1"	2"	6 1/2"	1'-10 1/4"	1'-7 3/4"	6 1/2"	2 1/16"		BP6
BP9	1	7'-2 15/16"	4 15/16"	11	6'-5"	5"	2'-2 3/8"	2'-0 13/16"	2"	6 7/16"	1'-10 1/2"	1'-7 1/2"	6 7/16"	2 1/16"		BP8
BP10	1	7'-2 15/16"	4 15/16"	11	6'-5"	5"	2'-2 1/2"	2'-0 11/16"	2"	6 7/16"	1'-10 1/2"	1'-7 1/2"	6 7/16"	2 1/16"		BP9
BP11	1	7'-2 15/16"	4 15/16"	11	6'-5"	5"	2'-1 9/16"	2'-1 5/8"	2"	6 7/16"	1'-9"	1'-9"	6 7/16"	2 1/16"		BP10
BP12	1	7'-2 15/16"	4 15/16"	11	6'-5"	5"	2'-3 1/16"	2'-0 1/8"	2"	6 7/16"	1'-9"	1'-9"	6 7/16"	2 1/16"		BP11
																BP12

- 7'-2 7/8" ~ BP3
- 7'-2 7/8" ~ BP4
- 7'-2 7/8" ~ BP5
- 7'-2 7/8" ~ BP6
- 7'-3" ~ BP8
- 7'-2 15/16" ~ BP9
- 7'-2 15/16" ~ BP10
- 7'-2 15/16" ~ BP11
- 7'-2 15/16" ~ BP12

ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP3'
 ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP4'
 ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP5'
 ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP6'
 ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP8'
 ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP9'
 ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP10'
 ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP11'
 ONE REQ'D ~ BALUSTER PANEL ASSEMBLY 'BP12'

RECEIVED
 OK'D BY: [Signature] OK'D BY: [Signature]
 JUL 9 2008
 RESUBMIT: [] APPROVED: [Signature]
 BY: [] DATE: []

ANODIZED
(SEE LB1 FOR NOTES)

PROJECT No. BRZ 1441(19) C/2 ITEM NO. 900.640
 APPROVED: [Signature] REC'D APPROVAL: [Signature]
 DRAWING: [Signature]

L.B. FOSTER COMPANY
 1016 QUEENSTERS ROAD
 PITTSBURGH, PENNSYLVANIA 15220

FOR: A. D. ROSSI CORPORATION
 VERMONT AGENCY OF TRANSPORTATION
 TOWN OF FOWAL, COUNTY OF BENNINGTON
 BRIDGE RAILING FOR BRIDGE #41, TH 24, CL3 (LOCAL)
 3L ALUM BRIDGE RAILING ~ BALUSTER PANEL DETAILS

MADE: CMS DATE 06/03/08 JOB No. AR0485 CUST. No. []
 CHECK BILL DATE 06/18/08 DRAWING: LBA4 REV. No. []