STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | SIGN DIMENSIONS WIDTH (in) | SIGN DIMENSIONS HEIGHT (in) | NEW & SALVAGED SIGNS "A" | NEW & SALVAGED SIGNS "B" | NEW & SALVAGED SIGNS SALV SIGN | NEW & SALVAGED SIGNS SALV TIS | EXIST POST RETAIN | EXIST POST SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | FLANGED CHANNEL lb/ft 2.0 | FLANGED CHANNEL lb/ft 3.0 | SQUARE STEEL (in) lb/ft 1.75 1.88 | SQUARE STEEL (in) lb/ft 2.0 2.16 | SQUARE STEEL (in) lb/ft 2.5 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3 | TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7 | TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD. 1.7 | TUBULAR STEEL Ø (in) FOUNDATION | TUBULAR STEEL Ø (in) lb/ft 3.0 7.6 | TUBULAR STEEL Ø (in) lb/ft 3.5 9.0 | TUBULAR STEEL Ø (in) lb/ft 4.0 10.8 | TUBULAR STEEL Ø (in) lb/ft 5.0 14.6 | W-SHAPE STEEL FTG. SIZE 24" | W-SHAPE STEEL FTG. SIZE 30" | W-SHAPE STEEL WEIGHT | W-SHAPE STEEL POST SIZE | REFLECTIVE SIGN REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | |
| 50+43 LT | STOP | 1 | 30 | 30 | 6.25 ~~5.2~~ | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | RI-1 | | E-143 |
| | 1000 1415 0402 | 1 | 6 | 8 | 0.33 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | VD-700 | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 50+64 RT | LEGAL LOAD LIMIT 24,000 POUNDS | 1 | 24 | 30 | 5 | | | | | | 1 | | | X | | | | | | | | | | | | | | | | | | | | VR-017 | | E-141 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | FT | FT | FT 28 | FT | FT | FT | | EA | LB | LB | LB | | LB | LB | LB | LB | | | | |
| TOTALS | SF ~~10.53~~ 11.58 | SF | EA. | SF | | | FT 28 | | | FT | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB |

PROJECT: ROCHESTER
PROJECT NO.: BRZ 1444 (20)

DESIGN FILE NAME: 87e048/Structures/se048trf.dgn
IPARM FILE NAME: se048tsa.i
SURVEYED BY: GILMAN
SQUAD LEADER: C.P. WILLIAMS
TRAFFIC SIGN SUMMARY SHEET

PLOT DATE: 25-JAN-2002
SURVEY DATE: 3/91
DRAWN BY: P.G. JARVIS
SHEET: 12 OF 52