



77+85 Lt Gravel Drive (24 ft)  
 Construct 12" Aggregate Shoulders, In Place (Mod)  
 (Crushed Slate)

77+66 Rt. Begin Special Ditch w/ Stone Fill, Type I

Section B-B (31' Lt)

77+50 Rt. f = 95°-00' Rt. Construct Gravel Drive (16 ft) 12" Aggregate Shoulders, In Place (See Section A-A, This Sheet)

77+48 Rt. Existing 18" CMP ~ Remove New 28" x 20" x 40" CSPR .064

77+32 Rt. ~ 77+33 Rt. Removal of Existing Fence

SECTION A-A (23' Lt)

77+62 Lt. Construct Mailbox Turnout Relocate Mailbox, Single Support

77+21 Rt. ~ 77+35 Rt. Construct Special Ditch w/ Stone Fill, Type I

77+10 Rt. Construct Gravel Drive (16 ft) 12" Aggregate Shoulders, In Place

Section A-A (29 ft Rt)

77+08 Rt. New 28" x 20" x 36" CSPR .064

76+90 Rt. ~ 77+14 Rt. Existing 15" HCOGMP ~ Remove (Care Shall Be Taken In Removing Existing Culvert, Its Culvert Shall Remain Property Of Property Owner)

76+98 Rt. END SPECIAL DITCH w/ STONE FILL, TYPE I

1170 Scott Hill Rd. TH #5

FROM STA. 76+90	TO STA. 77+70
PROJECT NAME BERLIN MAIN	NO. 1446-16200(23-5)
SURVEYED BY REED	PLOTTED 06/05/90
SHEET 23 OF 73 SHEETS	09/87 0076

SCALE 1" = 40 FEET