

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	TRAINING	EROSION CONTROL	UTILITIES-BID ITEMS AND FEDERAL/STATE PARTICIPATION	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
					170						170		LF	BEGIN OPTION AA						
					170						170		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215	4.78				
					170						170		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415	4.78				
					170						170		LF	18" CPEP(SL)	601.2615	4.78				
														END OPTION AA						
					3						3		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18	-				
					2						2		EACH	PRECAST REINFORCED CONCRETE MANHOLE WITH CAST IRON COVER	604.21	-				
							20				20		HR	POWER GRADER RENTAL	608.15	EST				
							20				20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST				
							20				20		HR	TRUCK RENTAL	608.37	EST				
							20				20		HR	LOADER RENTAL, TYPE I	608.40	EST				
					25						25		MGAL	DUST CONTROL WITH WATER	609.10	2				
					2				26		28		CY	STONE FILL, TYPE I	613.10	1				
					13						13		CY	STONE FILL, TYPE III	613.12	1				
									840		840		CY	RIPRAP, HEAVY TYPE	613.15	1				
					112						112		LF	VERTICAL GRANITE CURB	616.21	2				
					60						60		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	1.51				
					44						44		LF	REMOVAL OF EXISTING CURB	616.41	1				
					64						64		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	1				
					10						10		SF	DETECTABLE WARNING SURFACE	618.30	EST				
					4						4		EACH	YIELDING MARKER POSTS	619.17	-				
					125						125		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	2				
					3						3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-				
					4						4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 4 RAIL BOX BEAM	621.73	-				
					239						239		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	3				
					160						160		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST				
					500						500		HR	FLAGGERS	630.15	EST				
										1	1		LS	FIELD OFFICE-ENGINEERS	631.10	-				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	EST				
						520					520		HR	EMPLOYEE TRAINEESHIP	634.10	EST				
					1						1		LS	MOBILIZATION / DEMOBILIZATION	635.11	-				
					930						930		LF	4 INCH WHITE LINE	646.20	8				
					930						930		LF	4 INCH YELLOW LINE	646.21	8				
					27				315		342		SY	GEOTEXTILE UNDER STONE FILL	649.31	-				
							114				114		SY	GEOTEXTILE FOR SILT FENCE	649.51	1				
							50				50		LB	SEED	651.15	EST				
							10				10		LB	SEED, WINTER RYE	651.17	EST				
							50				50		LB	FERTILIZER	651.18	EST				

PROJECT NAME: BENNINGTON  
 PROJECT NUMBER: BRF 1000(16)  
 FILE NAME: z88j087bdr\_qs.dgn  
 PROJECT LEADER: R. HEBERT  
 DESIGNED BY: D. BURHANS/S. KELLER  
 QUANTITY SHEET #2  
 PLOT DATE: 8/8/2014  
 DRAWN BY: P. MCCLURE  
 CHECKED BY: D. BRYANT  
 SHEET 4 OF 75