



NOTES:

- SEE TRAFFIC CONTROL NOTES SHEET FOR ITEM PAYMENT DETAILS.
- 12" X 36" OBJECT MARKER TO BE INSTALLED AT END OF BARRIAR TAPER. STRIPES SLOPE DOWNWARD TOWARD THE SIDE OF THE BARRIER ON WHICH TRAFFIC IS TO PASS. BOTTOM OF SIGN SHALL BE 6" ABOVE TOP OF BARRIER. ATTACHMENT OF OBJECT MARKER POST TO BARRIER SHALL BE APPROVED BY THE ENGINEER.

LEGEND	
	WORK ZONE
	BARREL
	SIGN LOCATION, TEMPORARY MOUNTING
	TYPE III BARRICADE
	TYPE III BARRICADE (MOD.)
	ENERGY ABSORPTION ATTENUATOR
	TEMPORARY TRAFFIC BARRIER
	PAVEMENT MARKING REMOVAL
	RAISED PAVEMENT MARKINGS (RPM)
	DIRECTION OF TRAVEL
	TEMPORARY PAVEMENT MARKINGS
	TEMPORARY PAVEMENT
	DYCL DOUBLE YELLOW CENTER LINE
	TSYEL TEMPORARY SOLID YELLOW EDGE LINE
	TSWEL TEMPORARY SOLID WHITE EDGE LINE

PROJECT NAME: BENNINGTON
 PROJECT NUMBER: BRF 1000(16)
 FILE NAME: z88j087bdr_tcp01.dgn
 PROJECT LEADER: R. HEBERT
 DESIGNED BY: D. BURHANS
 TRAFFIC CONTROL PLAN - PHASE I
 PLOT DATE: 8/8/2014
 DRAWN BY: T. KELLEY
 CHECKED BY: D. BRYANT
 SHEET 20 OF 75

