

**REINFORCING STEEL SCHEDULE**

Project: RIPTON FH010-1(42)

Sheet: 1 of 1

By: S. G. FARNSWORTH

Date: 9/9/2010

ITEM	EACH	SIZE	LENGTH	MARK	TYPE	A	B	C	D	G	H	J	K
1		ADDITIONAL REBARS FOR ABUTMENT # 2 PLUS APPROACH SLABS											
2													
3		APPROACH SLAB											
4	22	16	4450	AS1601	STR								
5	32	16	3430	AS1602	STR								
6	14	16	380	AS1603	STR								
7	32	19	3430	AS1901	STR								
8	26	32	4875	AS3201	1	325	4450	--					
9													
10		ABUTMENT # 2 - ADDITIONAL REBAR											
11	20	16	3610	2A1601	STR								
12	2	16	3965	2A1603	19			3265	700		350		606
13	31	16	1160	2A1611	17		405	350	405				
14	14	16	6500	2A1612	STR								
15	21	16	3650	2A1620	STR								
16	21	16	2000	2A1621	STR								
17	21	16	2000	2A1622	STR								
18	14	16	7000	2A1623	STR								
19	14	16	6500	2A1624	STR								
20	5	16	2500	2A1625	17		700	1800	--				
21	3	16	2300	2A1626	STR								
22													
23	40	25	5285	2A2501	17		3610	1675	--				
24	48	25	3650	2A2502	STR								
25	16	25	3650	2A2504	STR								
26													
27													
28													

Estimated Weight = 4050 KG

6077