STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES																TOTALS			DESCRIPTIONS			
ROADWAY	APPR. SLAB #1	APPR. SLAB #2		SPAN #1	SPAN #2	SPAN #3		ABUT. #1	ABUT. #2		PIER #1	PIER #2		EROSION CONTROL	E & C ITMES	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER
																					BEGIN PIPE OPTIONS	
144																		144		LF	18" CAAP .075 (2-2/3X1/2)	601.0216
144																		144		LF	18" PCCSP .079 (2-2/3 X 1/2)	601.0416
144																		144		LF	18" CPEP	601.0915
56																		56		LF	36" CAAP .075 (2-2/3 X 1/2)	601.0246
56																		56		LF	36" PCCSP .109 (2-2/3 X 1/2)	601.0447
56																		56		LF	36" CPEP	601.0930
																					END PIPE OPTIONS	
20																		20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25
20																		20		MGAL	DUST CONTROL WITH WATER	609.10
20																		20		TON	DUST & ICE CONTROL WITH CALCIUM CHLORIDE	609.15
347								1	2									350		CY	STONE FILL, TYPE I	613.10
														10				10		CY	STONE FILL, TYPE I (MOD.-CHECK DAMS)	613.10
														10				10		CY	STONE FILL, TYPE I (MOD.-STABILIZED CONST. ENTRANCE)	613.10
								680	260		50	20						1010		CY	STONE FILL, TYPE IV	613.13
														1800				1800		LF	SNOW FENCE (MOD.-PDF)	620.70
333																		333		LF	HVY DUTY STEEL BEAM GUARD RAIL	621.21
4																		4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60
1																		1		EACH	ANCHOR FOR CABLE RAIL AT OPNGS	621.66
100																		100		LF	ALUMINUM APPROACH RAILING (ANODIZED BLACK)	621.74
200																		200		HR	FLAGGERS	630.15
															1			1		LS	FIELD OFFICE-ENGINEERS	631.10
															1			1		LS	TESTING EQUIPMENT - CONCRETE	631.16
															1			1		LS	TESTING EQUIPMENT - BITUMINOUS (MOD.)	631.17
															1			1		LU	FIELD OFFICE - TELEPHONE (NABI)	631.25
1																		1		LS	MOBILIZATION/DEMOBILIZATION	635.11
1295																		1295		LF	DURABLE 4" WHITE LINE	646.40
1210																		1210		LF	DURABLE 4" YELLOW LINE	646.41
32																		32		LF	DURABLE 24" STOP BAR	646.46
8																		8		EACH	DURABLE LETTER OR SYMBOL	646.50
1295																		1295		LF	TEMPORARY 4" WHITE LINE	646.60
1210																		1210		LF	TEMPORARY 4" YELLOW LINE	646.61
32																		32		LF	TEMPORARY 24" STOP BAR	646.66
8																		8		EACH	TEMPORARY LETTERS OR SYMBOLS	646.70
														1860				1860		SY	GEOTEXTILE UNDER STONE FILL	649.31
														350				350		SY	GEOTEXTILE FOR SILT FENCE	649.51
														70				70		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61
														30				30		LB	SEED	651.15
														20				20		LB	SEED-WINTER RYE	651.17
														200				200		LB	FERTILIZER	651.18
														1				1		TON	AGRICULTURAL LIMESTONE	651.20
														1				1		TON	HAYMULCH	651.25
														10				10		EACH	HAYBALES FOR EROSION CONTROL	651.26

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

PROJECT NAME: **HARTFORD**
PROJECT NUMBER: **BRO-BTN 2004 (1)**

FILE NAME: **s89j045quant.xls**
PROJECT MANAGER: **C.P. WILLIAMS**
DESIGNED BY: **K.M. HIGGINS**
QUANTITY SHEET #2

PLOT DATE: **12/9/98**
DRAWN BY: **M.LONGSTREET**
CHECKED BY: **K.M. HIGGINS**
SHEET **4** OF **97**