



NO.	QTY.	DESCRIPTION	MATERIAL	LENGTH	REMARKS	PART NO.
7A	4	ANCHORAGE CONNECTOR PLATES				
7ac1	4	1/2" X 6"	A36	1'-3"	END: 413-105	
7ac2	4	1/2" X 13 1/2"	A36	1'-6"	A132-105	
7B	4	ANCHORAGE PLATES				
7b1	4	1/4" X 6"	A36	1'-1 1/4"	A132-105	
7c	25	FIELD BOLTS				
7c1	25	1/4" HEX HEAD CAP SCREW	A305		(US) A153-HQS, HOGCAP	
7c2	25	1/4" HEX NUT	A305		(US) A153-HQS, HOGCAP	
7c3	25	1/4" FLAT WASHER	F436		(US) A153-HQS, HOGCAP	
7c4	25	1/4" LOCK WASHER	F844		(US) A153-HQS, HOGCAP	

NOTE: ALL MATERIAL SPECIFICATION DESCRIPTIONS ARE ASTM UNLESS OTHERWISE NOTED.

RECEIVED
 CK'D BY ELP OK'D BY RY
 AUG 07 2007
 RESUBMIT APPROVED ✓
 BY CPW DATE 8/17/07

SEE SHEET NO. 1 FOR GENERAL NOTES

NO.	DATE	BY	DESCRIPTION
1	7/20/07	ELP	ISSUED FOR CONSTRUCTION

LOCATION - TOWNS OF NEW HAVEN & MERRIBRIDGE
 BRIDGE - 26
 PROJECT - ROUTE NO. 917/91, CLS
 P.A. NO. - 2003-078 (2005)
 DESIGNER - VERMONT DEPARTMENT OF TRANSPORTATION
 CUSTOMER - CONTRACTORS CRANE SERVICE, LLC

SCALE: PANEL DETAILS
 ADDISON COUNTY, VT

DATE: 8/15/07
 SHEET: 1 OF 07

20388 1206

088-BR