

QUANTITY SHEET 3



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		T	AGRICULTURAL LIMESTONE	651.20				
								1			1		T	HAY MULCH	651.25				
								52			52		CM	TOPSOIL	651.35				
								213			213		SM	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								100			100		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								180			180		SM	TEMPORARY EROSION MATTING	653.20				
								2			2		CM	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								64			64		CM	VEHICLE TRACKING PAD	653.35				
								6			6		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
								155			155		M	BARRIER FENCE	653.50				
								150			150		M	PROJECT DEMARCATION FENCE	653.55				
						0.14					0.14		SM	TRAFFIC SIGNS, TYPE A	675.20				
						5					5		M	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						1					1		EACH	REMOVING SIGNS	675.50				
						2					2		EACH	DELINEATOR WITH STEEL POST	676.10				
						1					1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
						1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
									110		110		CM	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT)(FPQ)	900.608				
						4					4		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING) (TL-2)	900.620				
									1		1		EACH	SPECIAL PROVISION (MICROPILE VERIFICATION LOAD TEST)	900.620				
									75		75		M	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED STEEL TUBING/CONCRETE COMBINATION)	900.640				
									151		151		M	SPECIAL PROVISION (MICROPILE, CASED) (245 MM)	900.640				
									241		241		M	SPECIAL PROVISION (MICROPILE, UNCASD)(220 MM)	900.640				
									1		1		LS	SPECIAL PROVISION (FURNISHING EQUIPMENT FOR INSTALLING MICROPILES)	900.645				
						1					1		LS	SPECIAL PROVISION (MAINTENANCE OF EXISTING WASTEWATER FLOWS)	900.645				
						1					1		LS	SPECIAL PROVISION (MAINTENANCE OF EXISTING WATER FLOWS)	900.645				
									1		1		LS	SPECIAL PROVISION (SEWER MAIN ON BRIDGE)(200 MM)(DUCTILE IRON)	900.645				
						1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL ALL INCLUSIVE)	900.645				
									1		1		LS	SPECIAL PROVISION (WATER MAIN ON BRIDGE) (200 MM)(DUCTILE IRON PIPE)	900.645				
						1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
						1					1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
						60					60		SM	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675				
									295		295		SM	SPECIAL PROVISION (LONGITUDINAL DECK GROOVING)	900.675				
						462					462		T	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME:	READSBORO
PROJECT NUMBER:	BRF 0105 (3)
FILE NAME: s89j088/STR/s89088forms.dgn	PLOT DATE: 03/12/2012
PROJECT LEADER: J. LACROIX	DRAWN BY: G. ROKES
DESIGNED BY: W. PELLETIER	CHECKED BY: W. PELLETIER
QUANTITY SHEET #3	SHEET 8 OF 90