



1 - FABRIC TROUGH - 104FT1

- 1.) FABRIC DRAIN TROUGH SHALL BE 3-PLY PREFORMED FABRIC MATERIAL CONFORMING TO SECTION 561.2.8 AND SHALL BE CUT PRE-ASSEMBLY FROM ONE PIECE.
- 2.) DRIP BEAD OF FABRIC MATERIAL SHALL BE CEMENTED TO THE BOTTOM OF THE FABRIC TROUGH CONTINUOUS TO THE FULL LENGTH.

JOB NO.		DRAWING NO.		REV.			
519		104					
ITEM	QTY	MARK	MATERIAL	LENGTH	REMARKS	WT	PROCUREMENT NOTES
104FT1	1		FABRIC TROUGH				
6	R	1	3104	5-32 x 916 x 11 802 TROUGH	3 PLY FABRIC		
6	S	1	3104	5-32 x 25 x 180	3 PLY FABRIC DRIP BEAD		

4/2/13	REVISED DRIP BEAD	BP	TJB		
REV. DATE	REMARKS	DMN	CHK	RPVL	SHOP
MATERIAL:	SURFACE PREP. & PAINT:	HOLES:	SHOP BOLTS:		
DESCRIPTION: FABRIC TROUGH					
CASCO BAY STEEL STRUCTURES, INC. 1 WALLACE AVE. PHONE (207) 780-6722 SOUTH PORTLAND, ME 04106 FAX. (207) 780-6726					
STRUCTURE:	READSBORO VT. ROUTE TH-2 OVER WEST BRANCH OF DEERFIELD RIVER	DRAWN:	TJB	DATE:	03/13
		CHKD:	HBC	DATE:	03/13
LOCATION:	READSBORO, VERMONT	JOB NO.	519	DWG NO.	104
PROJ NO.	BRF D105(3)			REV.	△
CUSTOMER:	RENAUD BROS.				