

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES															TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES					
Non-Partic Telephone	Non-Partic Sewer	Partic. Water	Roadway	Full E+C	Approach Slab #1	Abutment #1		Pier		Abutment #2	Approach Slab #2	Employee Traineeship	Channel	Super-structure	Erosion Control	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS	
				201														201			LF	HVY DUTY STEEL BEAM GUARD RAIL	621.21			
				2														2			EACH	ANCHOR FOR STEEL BEAM RAIL	621.60			
				2														2			EACH	GUARD RAIL APPROACH SECTION, TYPE I (MOD)	621.70			
				2														2			EACH	GUARD RAIL APPR. SECTION,NETC 2 RAIL (MOD)	621.72			
				2														2			EACH	GUARD RAIL APPR. SECTION,NETC 4 RAIL (MOD)	621.73			
				168														168			LF	REMOVL AND DISP OF GUARD RAIL	621.80			
				1														1			MFBM	INSULATION BOARD	622.10			
				65														65			LF	DUCTS, CONCRETE ENCASED (2 - 4" PVC Type C Duct)	624.20			
				65														65			LF	DUCTS, CONCRETE ENCASED (3 - 4" PVC Type C Duct)	624.20			
				450														450			LF	DUCTS, CONCRETE ENCASED (6 - 4" PVC Type C Duct)	624.20			
				120														120			LF	DUCTS, CONCRETE ENCASED (9 - 4" PVC Type C Duct)	624.20			
				15														15			LF	DUCTS, CONCRETE ENCASED (12 - 4" PVC Type C Duct)	624.20			
				12														12			LF	SLEEVES FOR UTILITIES (6 - 4" GIP)	625.10			
				58														58			LF	SLEEVES FOR UTILITIES - 18"	625.10			
				1														1			LS	DUCTS ON BRIDGE (6 - 4" FIBERGLASS)	625.16			
				60														60			LF	SEAMLESS COPPER WATER TUBE - 3/4" TYPE K (MOD)	629.23			
				160														160			LF	DUCTILE, IRON PIPE, CEM LINED - 8" CL 52 (MOD)	629.24			
				160														160			LF	DUCTILE, IRON PIPE, CEM LINED - 12" CL 52 (MOD)	629.24			
				1														1			EACH	EXTENSION SERVICE BOX AND CURB STOP	629.25			
				2														2			EACH	GATE VALVE WITH VALVE BOX - 8"	629.27			
				1														1			EACH	GATE VALVE WITH VALVE BOX - 12" (MOD BUTTERFLY VALVE)	629.27			
				1														1			EACH	CORPORATION STOP - 3/4"	629.39			
				1														1			LS	TRANSFER TO NEW SYSTEM-WATER SYSTEM	629.42			
				4														4			EACH	AIR RELEASE - WATER (MANUAL)	629.43			
				1														1			LS	WATER MAIN ON BRIDGE - 12" (MOD 1)	629.60			
				1														1			LS	WATER MAIN ON BRIDGE - TEMP (MOD 2)	629.60			
				240														240			HR	UNIFORMED TRAFFIC OFFICERS	630.10			
				240														240			HR	FLAGGERS	630.15			
				1														1			LS	FIELD OFFICE-ENGINEERS	631.10			
				1														1			LS	TESTING EQUIPMENT - CONCRETE	631.16			
				1														1			LS	TESTING EQUIPMENT - BITUMINOUS	631.17			
				1														1			LU	FIELD OFFICE - TELEPHONE (NABI)	631.25			
				1560														1560			HR	EMPLOYEE TRAINEESHIP	634.10			
				1														1			LS	MOBILIZATION	635.10			
				1580														1580			LF	DURABLE 4" WHITE LINE	646.40			
				1530														1530			LF	DURABLE 4" YELLOW LINE	646.41			
				33														33			LF	DURABLE 24" STOP BAR	646.46			
				4														4			EACH	DURABLE LETTER OR SYMBOL	646.50			
				66														66			LF	DURABLE CROSSWALK W/DIAGONAL LINES	646.51			
				30														30			LF	DURABLE CROSSWALK W/DIAGONAL LINES (MOD)	646.51			
				1450														1450			LF	TEMPORARY 4" WHITE LINE	646.60			

PROJECT NAME: **Royalton**
PROJECT NUMBER: **BRZ 1444(22)**
FILE NAME: **sj099quant** PLOT DATE: **9/25/00**
PROJECT LEADER: **C. Williams** DRAWN BY: **C. Williams**
DESIGNED BY: **W. Symonds** CHECKED BY: **W. Symonds**
QUANTITY SHEET #3 SHEET **6** OF **118**