



RECEIVED  
 CKD BY WMS OK'D BY \_\_\_\_\_  
 APR 26 2001  
 RESUBMIT \_\_\_\_\_ APPROVED   
 BY CPW DATE 5/26/01

SHOP NOTE:  
 #1 = 3,000 PSI (MIN) @ STRIPPING  
 #2 = 5,000 PSI (MIN) @ 28 DAYS

MARK: R-CI	QTY.: 1	WT./TONS: 3.22	CU. YDS.: 1.59
------------	---------	----------------	----------------

MATERIALS LIST				REMARKS
ITEM	MARK	QTY.	DESCRIPTION	
1	EM-1	3	1/2" WASHER 1/2"x3"x3" (AASHTO 183, GR. 36) W/ (1) 1/2" HOLE (GALV)	FOR ERECTION
2	EM-2	3	1 1/4" x 1 1/4" ANCHOR BOLT (GALV) (ASTM A307, GR. C)	FOR ERECTION
3	EM-3	3	1 1/4" HEAVY HEX NUT (GALV)	FOR ERECTION
4	L-1	4	1T x 4 3/4" SWIFT LIFT LIFTERS (DAYTON)	
5				
6				
7				
8				
9				
10				

NOTES:  
 1. ALL SURFACES OF THE PRECAST CAPS (EXCLUDING FORM FACE) SHALL BE GIVEN A RUBBED FINISH PER VAOT STD. SPECIFICATIONS SUB-SECTION 501.16(a)(2).  
 2. ALL EDGES OF PRECAST CAPS SHALL BE FABRICATED TO BE VERTICAL IN THE FINAL ERECTED POSITION.

NO.	DATE	REVISION	B.L.
1	4-3-01	REVISED FOR APPROVAL	

DRAWN: <u>B.M. LOPEZ</u>
DESIGNED: <u>E.J. BROD</u>
CHECKED: _____
APPROVED: _____

J.P. CARRARA & SONS INC.  
 Precast & Prestress Manufacturer  
 2464 CASE ST., MIDDLEBURY, VERMONT 05753  
 Phone: (802)388-0361 Fax: (802)388-9010

Beck & Bellucci, Inc.  
 10 SALISBURY ROAD, PO BOX 429  
 FRANKLIN, NEW HAMPSHIRE 03235

Project Name:  
**ROYALTON BRIDGE**  
 BRZ 1444 (22)  
 ROYALTON, VERMONT

SCALE: NOTED JOB #: 23111-00  
 DATE: 2-20-01 SHEET #: PCI

PIER TOWER CAP DETAILS