



RECEIVED
 OK'D BY WMS OK'D BY _____
 APR 26 2001
 RESUBMIT _____ APPROVED
 BY OPW DATE 5/24/01

SHOP NOTE:
 Pci = 5,000 PSI (MIN.) @ STRIPPING
 Pcs = 5,000 PSI (MIN.) @ 28 DAYS

MARK: **R-C3** QTY.: 1 WT./TONS: 1.56 CU. YDS.: 0.77

MATERIALS LIST				
ITEM	MARK	QTY.	DESCRIPTION	REMARKS
1	EM-1	2	E WASHER 1/2"x3"x3" (AASHTO 103, GR. 36) W/ (1) 1/2" HOLE (GALV.)	FOR ERECTION
2	EM-2	2	1 1/4" x 1-4" ANCHOR BOLT (GALV.) (ASTM A307, GR. C)	FOR ERECTION
3	EM-3	2	1 1/4" HEAVY HEX NUT (GALV.)	FOR ERECTION
4	L-1	4	1T x 4 3/4" SWIFT LIFT LIFTERS (DAYTON)	
5				
6				
7				
8				
9				
10				

NOTES:
 1. ALL SURFACES OF THE PRECAST CAPS (EXCLUDING FORM FACE) SHALL BE GIVEN A RUBBED FINISH PER VAOT STD. SPECIFICATIONS SUB-SECTION 501.16(a)2.
 2. ALL EDGES OF PRECAST CAPS SHALL BE FABRICATED TO BE VERTICAL IN THE FINAL ERECTED POSITION.

DRAWN: B.M. LOPEZ
 DESIGNED: E.J. BROD
 CHECKED: _____
 APPROVED: _____

J.P. CARRARA & SONS INC.
 Precast & Prestress Manufacturer
 2484 CASE ST., MIDDLEBURY, VERMONT 05753
 Phone: (802) 388-6361 Fax: (802) 388-9010
 Double-Tees Hollow-Core Plank Flat Panels

BECK & BELLUCCI, INC.
 10 SALISBURY ROAD, PO BOX 429
 FRANKLIN, NEW HAMPSHIRE 03235

Project Name:
ROYALTON BRIDGE
 BRZ 1444 (22)
 ROYALTON, VERMONT
PIER TOWER CAP DETAILS

SCALE: NOTED JOB #: 23111-00
 DATE: 2-20-01 SHEET #: PCS

NO.	DATE	REVISION
1	4-3-01	REVISED FOR APPROVAL