

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
														ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
															1		LS	TRANSFER TO NEW SYSTEM - WATER SYSTEM (MOD.)	629.42			
															1		LS	WATER MAIN ON BRIDGE	629.60			
															100	100	HR	FLAGGERS	630.15			
															1	1	LS	FIELD OFFICE-ENGINEERS	631.10			
															1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16			
															1	1	LS	TESTING EQUIPMENT - BITUMINOUS (MOD.)	631.17			
															1	1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25			
															1	1	LS	MOBILIZATION	635.10			
															650	650	LF	4" WHITE LINE	646.20			
															650	650	LF	4" YELLOW LINE	646.21			
															100	100	SY	GEOTEXTILE UNDER STONE FILL	649.31			
															222	222	SY	GEOTEXTILE FOR SILT FENCE	649.51			
															60	60	LB	SEED	651.15			
															10	10	LB	SEED-WINTER RYE	651.17			
															500	500	LB	FERTILIZER	651.18			
															2	2	TON	AGRICULTURAL LIMESTONE	651.20			
															2	2	TON	HAYMULCH	651.25			
															25	25	EACH	HAY BALES FOR EROSION CONTROL	651.26			
															20	20	SY	SODDING	651.30			
															16	16	CY	TOPSOIL	651.35			
															1	1	LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10			
															250	250	HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20			
															1	1	LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30			
															100	100	SY	EROSION MATTING	654.10			
															4	4	EA	REMOVING SIGNS	675.50			

PROJECT NAME: **Barre City**
PROJECT NUMBER: **HDP 9281 (1)**
FILE NAME: str5/92j099/sj099qua.xls
PROJECT MANAGER: C. Keller
DESIGNED BY: K. Rutter
QUANTITY SHEET #2

PLOT DATE: 12/9/98
DRAWN BY: K. Rutter
CHECKED BY: T. Sumner
SHEET 5 OF 58