

# QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES										TOTALS			DESCRIPTIONS		DETAILED SUMMARY OF QUANTITIES			
ROADWAY	CHANNEL	ABUTMENT #1	ABUTMENT #2	SUPERSTR UCTURE	APPROACH SLAB #1	APPROACH SLAB #2	EROSION CONTROL	FULL C.E. ITEMS	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
	870										870		CM	STONE FILL, TYPE IV	613.13			
2											2		EACH	RELOCATE MAIL BOX, SINGLE SUPPORT	617.10			
10											10		M	REMOVING AND RESETTING FENCE	620.50			
15											15		M	REMOVAL OF EXISTING FENCE (MOD.)	620.55			
							225				225		M	SNOW FENCE (MOD. - PDF)	620.70			
							85				85		M	SNOW FENCE (MOD. - ARCH)	620.70			
52											52		M	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21			
4											4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.80			
24											24		M	REMOVL AND DISP OF GUARD RAIL	621.80			
18											18		M	REMOVL AND DISP OF GUARD RAIL (MOD.)	621.80			
12											12		EACH	REMOVL AND DISP OF GUIDE POSTS	621.81			
50											50		HR	UNIFORMED TRAFFIC OFFICERS	630.10			
								1			1		LS	FIELD OFFICE-ENGINEERS	631.10			
								1			1		LS	TESTING EQUIPMENT - CONCRETE	631.16			
								1			1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17			
								1			1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25			
1											1		LS	MOBLIZATION/DEMOLIZATION	635.11			
1											1		LS	TRAFFIC CONTROL	641.10			
494											494		M	100 mm WHITE LINE	648.20			
482											482		M	100 mm YELLOW LINE	648.21			
7											7		M	300 mm WHITE LINE	648.24			
	600										600		SM	GEOTEXTILE UNDER STONE FILL	649.31			
							150				150		SM	GEOTEXTILE FOR SILT FENCE	649.51			
							5				5		KG	SEED	651.15			
							5				5		KG	SEED-WINTER RYE	651.17			
							90				90		KG	FERTILIZER	651.18			
							1				1		T	AGRICULTURAL LIMESTONE	651.20			
							1				1		T	HAY MULCH	651.25			
							10				10		EACH	HAY BALES FOR EROSION CONTROL	651.26			
							80				80		CM	TOPSOIL	651.35			
	350										350		SM	GRUBBING MATERIAL	651.40			
							1				1		LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10			
							50				50		HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20			
							1				1		LU	MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30			
							70				70		SM	EROSION MATTING	654.10			
7											7		EACH	EVERGREEN TREES (WHITE PINE) (2.5M - 4.0M)	656.20			
2.2											2.2		SM	TRAFFIC SIGNS, TYPE A	675.20			
9											9		M	BEGIN SIGN POST OPTION				
9											9		M	FLANGED CHANNEL SIGN POSTS	675.301			
													M	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341			
2											2		EACH	END SIGN POST OPTION				
													EACH	REMOVING SIGNS	675.50			

PROJECT NAME: **SUNDERLAND**  
 PROJECT NUMBER: **BRF 0114(2)**  
 FILE NAME: /PW/93j009/sj009qnt.xls  
 PROJECT MANAGER: R.R. WHITCOMB  
 DESIGNED BY: D. BONNEAU  
 QUANTITY SHEET #2

PLOT DATE: 7/21/2004  
 DRAWN BY: J. GILMORE  
 CHECKED BY: C. CARLSON  
 SHEET 5 OF 67