GENERAL NOTES:

1. ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO STATE OF VERMONT AGENCY OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION DATED ~~1990~~ 2001, AND ITS LATEST REVISIONS, AND THE AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, DATED 1996, AND ITS LATEST REVISIONS.

2. THESE SHOP DRAWINGS WERE PREPARED IN ACCORDANCE WITH THE CONTRACT PLANS AND SPECIFICATIONS. THE D.S. BROWN COMPANY DOES NOT ACCEPT LIABILITY FOR THE DESIGN OF THE PRODUCTS DETAILED IN THESE SHOP DRAWINGS.

4. THE D.S. BROWN COMPANY IS TO ONLY SUPPLY THE PARTS SHOWN ON THIS DRAWING.

5. SURFACES TO BE GALVANIZED. PRIOR TO GALVANIZING, ALL CORNERS AND EDGES OF STEEL PLATES, SHAPES, ETC., SHALL BE GROUND TO A 1/16 INCH RADIUS.

6. WELDING PROCEDURES SHALL BE ESTABLISHED BY THE CONTRACTOR TO RESTRICT THE MAXIMUM TEMPERATURE REACHED BY BONDED PTFE SURFACES TO A MAXIMUM OF 300°F (149°C). TEMPERATURES SHALL BE DETERMINED BY TEMPERATURE INDICATING WAX PENCILS OR OTHER SUITABLE MEANS.

7. GALVANIZED NUTS SHALL BE LUBRICATED WITH A LUBRICANT CONTAINING A VISIBLE DYE THAT WILL PROVIDE VISUAL VERIFICATION OF THE LUBRICANT DURING INSTALLATION.

STRUCTURES COPY

RECEIVED
CK'D BY JWP CK'D BY _____
APR 29 2004
RESUBMIT _____ APPROVED As Noted
BY RRW DATE 5-12-04

REV.	DESCRIPTION	DATE	DET.	CKD.

D.S. BROWN
300 E. CHERRY STREET
NORTH BALTIMORE, OHIO 45872
419.257.3561
FAX: 419.257.0332

4201 NOREX DRIVE
CHASKA, MINNESOTA 55318
952.368.3000
FAX: 952.448.7000

DSBROWN.COM

LOCATION — T.H. 4 OVER BLACK RIVER CAVENDISH
BRIDGE — 12
PROJECT — BHO 1442 (22)
F.A.P. NO. — –
P.O. NO. — 4013
DESIGNER — VANASSE HANGEN BRUSTLIN, INC.
CUSTOMER — MILLER CONSTRUCTION

ITEM	QUANTITY
–	–
–	–
–	–
–	–
–	–
–	–
–	–
–	–
–	–
–	–

DESCRIPTION: GENERAL NOTES
WINDSOR COUNTY, VERMONT

SCALE:	DRAWN BY:	CHECKED BY:	DATE:	
N.T.S.	B.COPPUSE	E.KELLEY	4/22/04	–
PROJECT NUMBER:	PRODUCT CODE:	RELEASE:	SHEET:	
11091	1106	1	GN1	

040 BB