

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
Super Struct.	Abut. #1	Abut. #2	Apprch. Slab #1	Apprch. Slab #2	Roadway	E & C Items	Erosion Control	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS				
					1					1		LS	CLEARING AND GRUBBING (INCL. INDV. TREES & STUMPS)	201.10							
					145					145		CM	COMMON EXCAVATION	203.15							
	30	30								60		CM	UNCLASSIFIED CHANNEL EXCAVATION	203.27							
							10			10		CM	TRENCH EXCAVATION OF EARTH	204.20							
	150									150		CM	STRUCTURE EXCAVATION (ABUTMENT #1)	204.25							
		150								150		CM	STRUCTURE EXCAVATION (ABUTMENT #2)	204.25							
	50	70								120		CM	GRANULAR BACKFILL FOR STRUCTURES	204.30							
					130		10			140		CM	SUBBASE OF GRAVEL	301.15							
					40					40		CM	AGGREGATE SURFACE COURSE	401.10							
27	37	36								100		CM	CONCRETE, HIGH PERFORMANCE CLASS B	501.34							
	2470	2630								5100		KG	REINFORCING STEEL	507.15							
	13	14								27		M	DRILLING AND GROUTING DOWELS	507.16							
2520										2520		KG	EPOXY COATED REINFORCING STEEL	507.17							
21	8	7								36		L	WATER REPELLENT (MOD.-SILANE)	514.10							
23										23		M	BRIDGE RAILING - HD STEEL BEAM/FASCIA MOUNTED (GALVANIZED)	525.41							
					1					1		LS	ONE-WAY TEMPORARY BRIDGE(50 SM-EST.)(MOD.)	528.10							
1										1		EACH	REMOVAL OF STRUCTURE(39 SM-EST.)	529.15							
							5			5		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25							
					1					1		T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15							
	2						10			12		CM	STONE FILL, TYPE I	613.10							
							10			10		CM	STONE FILL, TYPE I (MOD. - CHECK DAM)	613.10							
							10			10		CM	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10							
	50	60								110		CM	STONE FILL, TYPE IV	613.13							
					1					1		EACH	RELOCATE MAIL BOX, MULTIPLE SUPPORT	617.12							
							12			12		M	SNOW FENCE (MOD. - PDF)	620.70							
					49					49		M	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21							
					4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60							
					23					23		M	REMOVL AND DISP OF GUARD RAIL	621.80							
					25					25		M	TEMPORARY TRAFFIC BARRIER	621.90							
					200					200		HR	FLAGGERS	630.15							
						1				1		LS	FIELD OFFICE-ENGINEERS	631.10							
						1				1		LS	TESTING EQUIPMENT - CONCRETE	631.16							
						1				1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25							
					1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11							
					1					1		LS	TRAFFIC CONTROL	641.10							
					10					10		M	DURABLE 100 mm YELLOW LINE	646.41							
					10					10		M	TEMPORARY 100 mm YELLOW LINE	646.61							
					5					5		SM	BLACK PAVEMENT MARKING MASKING TAPE	646.86							
	35	40								75		SM	GEOTEXTILE UNDER STONE FILL	649.31							
							82			82		SM	GEOTEXTILE FOR SILT FENCE	649.51							
							10			10		KG	SEED	651.15							
							5			5		KG	SEED-WINTER RYE	651.17							
							50			50		KG	FERTILIZER	651.18							

PROJECT NAME: **Vershire**
 PROJECT NUMBER: **BRO 1444 (32)**
 FILE NAME: sj027qs1.xls PLOT DATE: 3/14/2006
 PROJECT LEADER: C.P. Williams DRAWN BY: P.K.PERRY
 DESIGNED BY: P.K.PERRY CHECKED BY: K.M. Higgins
 QUANTITY SHEET #1 SHEET 3 OF 34