

QUANTITY SHEET 2



| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | TOTALS | | | DESCRIPTIONS | | | DETAILED SUMMARY OF QUANTITIES | | |
|---------------------------------|---------|---------|---------|------|----------------------|-----------------|----|-----|--|--------|-------------|-------|--------------|--|-------------|--------------------------------|------|-------|
| FULL E&C ITEMS | ROADWAY | ABUT #1 | ABUT #2 | DECK | TEMP EROSION CONTROL | EROSION CONTROL | | | | ROUND | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | QUANTITIES | UNIT | ITEMS |
| | 1 | | | | | | | | | | 1 | | LS | TRAFFIC CONTROL | 641.10 | | | |
| | | 65 | 139 | | | 6 | | | | | 210 | | SM | GEOTEXTILE UNDER STONE FILL | 649.31 | | | |
| | | | | | | 220 | | | | | 220 | | SM | GEOTEXTILE FOR SILT FENCE | 649.51 | | | |
| | | | | | | | 20 | | | | 20 | | KG | SEED | 651.15 | | | |
| | | | | | | | 20 | | | | 20 | | KG | SEED-WINTER RYE | 651.17 | | | |
| | | | | | | | | 130 | | | 130 | | KG | FERTILIZER | 651.18 | | | |
| | | | | | | | | 2 | | | 2 | | T | AGRICULTURAL LIMESTONE | 651.20 | | | |
| | | | | | | | | 2 | | | 2 | | T | HAY MULCH | 651.25 | | | |
| | | | | | | | | 10 | | | 10 | | EACH | HAY BALES FOR EROSION CONTROL | 651.26 | | | |
| | 120 | | | | | | | | | | 120 | | CM | TOPSOIL | 651.35 | | | |
| | | | | | | | | 135 | | | 135 | | SM | GRUBBING MATERIAL | 651.40 | | | |
| | | | | | | | | 1 | | | 1 | | LS | EROSION PREVENTION & SEDIMENT CONTROL PLAN | 652.10 | | | |
| | | | | | | | | 40 | | | 40 | | HR | MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN | 652.20 | | | |
| | | | | | | | | 1 | | | 1 | | LU | MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (N.A.B.I.) | 652.30 | | | |
| | | | | | | 2390 | | 200 | | | 2590 | | SM | EROSION MATTING | 654.10 | | | |
| | 3 | | | | | | | | | | 3 | | SM | TRAFFIC SIGNS, TYPE A | 675.20 | | | |
| | 19 | | | | | | | | | | 19 | | M | FLANGED CHANNEL SIGN POST | 675.301 | | | |

PROJECT NAME: **Charleston**
 PROJECT NUMBER: **BRO 1449 (22)**
 FILE NAME: Quantities.xls
 PROJECT MANAGER: M. EVANS-MONGEON
 DESIGNED BY: G. COLGROVE
 IPARM: sj051qty2.i
 PLOT DATE: 12/19/05
 DRAWN BY: G. ROKES
 CHECKED BY: G. COLGROVE
 SHEET 6 OF 50