

QUANTITY SHEET 2



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL E & C ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								100			100		M	WOVEN WIRE FENCE WITH WOOD POSTS	620.26				
							65				65		M	REMOVING AND RESETTING FENCE	620.50				
							6				6		M	PLANK RAIL	621.15				
							167.6				167.6		M	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
							72.4				72.4		M	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
							6				6		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							13				13		EACH	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81				
							30				30		M	SLEEVES FOR UTILITIES (2 X 50 MM)	625.10				
							4				4		EACH	EXTENSION SERVICE BOX AND CURB STOP (19 MM)	629.25				
							30				30		M	PLASTIC WATER PIPE, RIGID (19 MM)	629.33				
							1				1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42				
							100				100		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							300				300		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1	1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
							230				230		M	100 MM WHITE LINE	646.20				
							230				230		M	100 MM YELLOW LINE	646.21				
							5				5		M	600 MM STOP BAR	646.26				
									530		530		SM	GEOTEXTILE UNDER STONE FILL	649.31				
								30			30		SM	GEOTEXTILE FOR SILT FENCE	649.51				
								450			450		SM	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								20			20		KG	SEED	651.15				
								10			10		KG	SEED, WINTER RYE	651.17				
								200			200		KG	FERTILIZER	651.18				
								1			1		T	AGRICULTURAL LIMESTONE	651.20				
								1			1		T	HAY MULCH	651.25				
								130			130		CM	TOPSOIL	651.35				
								790			790		SM	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								30			30		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								1100			1100		SM	TEMPORARY EROSION MATTING	653.20				
								10			10		CM	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								30			30		CM	VEHICLE TRACKING PAD	653.35				
								230			230		M	BARRIER FENCE	653.50				
								120			120		M	PROJECT DEMARCATION FENCE	653.55				

PROJECT NAME: GUILFORD
 PROJECT NUMBER: BRO 1442 (24)
 FILE NAME: sj070qty.dgn PLOT DATE: 04/30/2008
 PROJECT MANAGER: R. WHITCOMB DRAWN BY: T. LACKEY
 DESIGNED BY: T. LACKEY CHECKED BY: R. WHITCOMB
 QUANTITY SHEET #2 SHEET 6 OF 59