STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES

TEMP BRIDGE	BRIDGE	NON-GOVM'T PART.	RIGHT-OF-WAY	TRAINING	LAND-SCAPING	EROSION CONTROL	FULL E & C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
								1	1	LS	CLEARING AND GRUBBING (INCLUDING INDIVIDUAL TREES AND STUMPS)	201.10	
								900	900	CY	COMMON EXCAVATION	203.15	
								5320	5320	CY	EARTH BORROW	203.30	
								3100	3100	CY	SAND BORROW	203.31	
								8000	8000	SY	FINE GRADING - SUBGRADE	203.40	
								220	220	CY	TRENCH EXCAVATION OF EARTH	204.20	
	900								900	CY	STRUCTURE EXCAVATION	204.25	
	860								860	CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	
								250	250	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	
								3900	3900	CY	SUBBASE OF DENSE-GRADED CRUSHED STONE	301.35	
								20	20	CY	AGGREGATE SURFACE COURSE	401.10	
								400	400	CWT	EMULSIFIED ASPHALT	404.65	
	72							2100	2172	T	BITUMINOUS PAVEMENT	406.25	
								4	4	CY	CONCRETE, CLASS D (MODIFIED) FLOWABLE FILL	501.31	
	103								103	CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33	
	362								362	CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	
	1								1	LS	FURNISHING EQUIPMENT FOR PILE DRIVING	504.10	
	665								665	LF	STEEL PILING (HP 12x74)	505.16	
	105310								105310	LB	STRUCTURAL STEEL (PLATE GIRDER)	506.55	
	36380								36380	LB	REINFORCING STEEL	507.15	
	31020								31020	LB	EPOXY COATED REINFORCING STEEL	507.17	
	1								1	LS	SHEAR CONNECTORS (1030 STUDS)	508.15	
	19								19	GAL	WATER REPELLENT	514.10	
	34								34	LF	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG JOINT)	516.10	
	436								436	SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20	
	200								200	LF	BRIDGE RAILING - HDSB/FASCIA MOUNTED/HANDRAIL	525.43	
1									1	LS	TWO WAY TEMPORARY BRIDGE	528.11	
	215								215	SY	REMOVAL OF BRIDGE PAVEMENT	529.10	
	1								1	LS	REMOVAL OF STRUCTURE	529.15	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DATUM
VERTICAL NAVD 88
HORIZONTAL NAD 83 (1996)

QUANTITY SHEET

PROJECT NAME: SHELBURNE
PROJECT NUMBER: BRO 1445(30)

FILE NAME: M:\1595402 Bostwick\HWY\DRAW\QUANSUM\totsum01.dgn
PROJECT LEADER: MBZ
DESIGNED BY: DMB
CHECKED BY: MDL
PLOT DATE: 04-AUG-2003
DRAWN BY: MJF
SHEET 13 OF 73