STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES

TEMP BRIDGE	BRIDGE	NON-GOVM'T PART.	RIGHT-OF-WAY	TRAINING	LAND-SCAPING	EROSION CONTROL	FULL E & C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
	10								10	EA	BEARING DEVICE ASSEMBLY	531.10	
								70	70	LF	15" CPEP PIPE	601.0910	
								140	140	LF	18" CPEP PIPE	601.0915	
								2	2	EA	PRC CURB DROP INLET WITH CAST IRON GRATE	604.30	
								10	10	HR	ROADWAY PATROL MAINTENANCE	607.10	
								10	10	HR	BULLDOZER RENTAL, TYPE I (NABI)	608.10	
								10	10	HR	POWER GRADER RENTAL (NABI)	608.15	
								10	10	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I (NABI)	608.25	
								10	10	HR	TRUCK RENTAL (NABI)	608.37	
								10	10	HR	LOADER RENTAL, TYPE I (NABI)	608.40	
								250	250	MGAL	DUST CONTROL WITH WATER	609.10	
								2	2	T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	
						25		85	110	CY	STONE FILL TYPE I	613.10	
	510								510	CY	STONE FILL, TYPE II	613.11	
	35							40	75	LF	VERTICAL GRANITE CURB	616.21	
								1	1	EA	RELOCATE MAILBOX	617.10	
								5	5	EA	YIELDING MARKER POST	619.17	
								5	5	EA	REMOVING AND RESETTING BOUNDARY MARKERS	619.20	
								250	250	LF	REMOVING AND RESETTING FENCE	620.50	
								800	800	LF	STEEL BEAM GUARDRAIL	621.20	
	100							100	200	LF	HEAVY DUTY STEEL BEAM GUARDRAIL	621.21	
								4	4	EA	ANCHOR FOR STEEL BEAM GUARDRAIL	621.60	
								670	670	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	
								5	5	EA	GUIDE POSTS	621.85	
								3	3	EA	SETTLEMENT PLATFORMS	623.21	
								200	200	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
								650	650	HR	FLAGGERS	630.15	
							1		1	LS	FIELD OFFICE - ENGINEERS	631.10	
							1		1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
							1		1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DATUM

VERTICAL NAVD 88
HORIZONTAL NAD 83 (1996)

QUANTITY SHEET

PROJECT NAME: SHELBURNE
PROJECT NUMBER: BRO 1445(30)

FILE NAME: M:\1595402 Bostwick\HWY\DRAW\QUANSUM\totsum01.dgn
PROJECT LEADER: MBZ
DESIGNED BY: DMB
CHECKED BY: MDL
PLOT DATE: 04-AUG-2003
DRAWN BY: MJF
SHEET 14 OF 73