STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES

TEMP BRIDGE	BRIDGE	NON-GOVM'T PART.	RIGHT-OF-WAY	TRAINING	LAND-SCAPING	EROSION CONTROL	FULL E & C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
							1		1	LS	FIELD OFFICE - TELEPHONE (NABI)	631.25	
								1	1	LS	MOBILIZATION	635.10	
								3300	3300	LF	4" WHITE LINES	646.20	
								3300	3300	LF	4" YELLOW LINES	646.21	
	695							450	1145	SY	GEOTEXTILE UNDER STONE FILL	649.31	
						500			500	SY	GEOTEXTILE FOR SILT FENCE	649.51	
						50			50	LB	SEED-WINTER RYE	651.17	
						105			105	LB	SEED	651.15	
						900			900	LB	FERTILIZER	651.18	
						4			4	T	AGRICULTURAL LIMESTONE	651.20	
						4			4	T	HAY MULCH	651.25	
						50			50	EA	HAYBALES FOR EROSION CONTROL	651.26	
								475	475	CY	TOPSOIL	651.35	
						1			1	LS	EROSION AND SEDIMENT CONTROL PLAN	652.10	
						200			200	HR	MONITORING EROSION AND SEDIMENT CONTROL PLAN	652.20	
						1			1	LS	FIELD MAINT. OF EROSION & SEDIMENT CONTROL PLAN	652.30	
						360			360	SY	EROSION MATTING	654.10	
								5	5	SF	TRAFFIC SIGNS, TYPE A	675.20	
								40	40	LF	FLANGED CHANNEL SIGN POSTS	675.301	
								8	8	EA	REMOVING SIGNS	675.50	
								3	3	EA	ERECTING SALVAGED SIGNS	675.60	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DATUM
VERTICAL NAVD 88
HORIZONTAL NAD 83 (1996)

QUANTITY SHEET

PROJECT NAME: SHELBURNE
PROJECT NUMBER: BRO 1445(30)

FILE NAME: m:\1595402 Bostwick\HWY\DRAW\QUANSUM\totsum01.dgn
PROJECT LEADER: MBZ
DESIGNED BY: DMB
CHECKED BY: MDL
PLOT DATE: 04-AUG-2003
DRAWN BY: MJF
SHEET 15 OF 73