

QUANTITY SHEET 3



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	EROSION CONTROL	UTILITIES	UTILITIES (NO FEDERAL/STATE)	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					16					16		CM	VEHICLE TRACKING PAD	653.35				
					3					3		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
					26					26		M	BARRIER FENCE	653.50				
					120					120		M	PROJECT DEMARCATION FENCE	653.55				
				1.04						1.04		SM	TRAFFIC SIGNS, TYPE A	675.20				
				9						9		M	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
				4						4		EACH	REMOVING SIGNS	675.50				
								65		65		M	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED HDSB/FASCIA MOUNTED,HAND RAIL,PAINTED BLACK)	900.640				
				1						1		LS	SPECIAL PROVISION (REMOVE AND REPLACE RESIDENTIAL WALKWAY)	900.645				
						1				1		LS	SPECIAL PROVISION (SEWER MAIN ON BRIDGE) (100MM)	900.645				
						1				1		LS	SPECIAL PROVISION (TRANSFER TO TEMPORARY SYSTEM, SANITARY SEWER)	900.645				
							1			1		LS	SPECIAL PROVISION (WATER MAIN ON BRIDGE)(200MM)	900.645				
				1						1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
				1						1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
				227				52		279		T	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: READSBORO
 PROJECT NUMBER: BRO 1441(25)
 FILE NAME: s94j070excet.dgn PLOT DATE: 01/19/2010
 PROJECT LEADER: C.P.WILLIAMS DRAWN BY: D.D.BEARD
 DESIGNED BY: H.LSALLS CHECKED BY: R.S.YOUNG
 QUANTITY SHEET #3 SHEET 6 OF 60