



Production Joint Welding Procedure Specification (D1.5-02)

Procedure No: B-FSV-01 Date Issued: 3-28-08 Revision No: 0 Rev. Date: _____

Contractor (Fabricator) D. S. Brown Company Prepared by: Brad Streeter, Quality Assurance Manager

1. Non-Fracture Critical Fracture Critical WPS Expiration Date: 3-6-13
2. Qualified in accordance with: AWS D1.5- 2002 (5.13)
 Referenced PQR No(s). PQR-FCAW-01-(08)
 Referenced FWST No(s). N/A
3. Material specification(s) ASTM A709 Gr. 36, 50, 50W
4. Material Thickness (es) Unlimited
5. Welding process FCAW
6. Manual , machine , or semiautomatic
7. Position(s) of welding 1G
8. Filler metal specification AWS A5.20
9. Filler metal class and brand name E71T-1CH8 (UltraCore71C)
10. Flux class & brand N/A, Type N/A
11. Shielding gas 100% CO2 Flow rate 45 CFH
12. Single pass Or multiple pass
13. Single arc Or multiple arc
14. Welding Current DCEP
15. Polarity Reverse
16. Welding progression Stringers
17. Root treatment Clean to bright sound metal and per AWS D1.5 (3.2.1 & 3.11)
18. Postheat treatment N/A
19. Calculated Heat Input (KJ/in) Min 32.2 KJ/in Max 45.8 KJ/in
20. Electrode extension (electrical stickout) 3/4"

For DOT Approval

TRANS RECEIVED

OK'D BY _____ OK'D BY JUC

NOV 17 2008

APPROVED

BY _____ DATE 12/29/08

Weld size (in)	Pass No(s)	Electrode Size (in)	Welding Process Variables		Travel Speed (IPM)
			AMPS	VOLTS	
**1/4"	1	1/16"	257-295	26.1-29.5	11.4-12.5
5/16"	1-2	1/16"	257-295	26.1-29.5	11.4-12.5
3/8"	2-3	1/16"	257-295	26.1-29.5	11.4-12.5
1/2"	4-5	1/16"	257-295	26.1-29.5	11.4-12.5
5/8"	5-6	1/16"	257-295	26.1-29.5	11.4-12.5
3/4"	5-8	1/16"	257-295	26.1-29.5	11.4-12.5

Joint Detail (C-P2-GF)
Show all dimensions, weld sizes, passes, and AWS symbols

T1 = 1/4" min.
 T2 = Unlimited
 f = 1/8" min.
 R = 0
 alpha = 60°
 S = Groove Prep Depth
**** T1 & T2 equal to or less than 3/4" for 1/4" welds.**

For Butt Joints see AWS 2.14

Prepared By: [Signature] DSB QA Manager

Project: TH 62 OVER WEST RIVER

DSB Job: 27177-1011

Base Metal Thickness range	Minimum Preheat (°F)	Max Preheat & Interpass (°F)
≤ 3/4"	50°F	450°F
>3/4" to ≤1.5"	70°F	450°F
>1.5" to ≤2.5"	150°F	450°F
>2.5"	225°F	450°F

Note: When this procedure is used for A709Gr50W materials, it shall be limited to 5/16" single pass or material be coated.