


- STON UTILITY ANCHOR " OXFORD A1750-7" (1ST IN).
- CONTROLLING CONDITION, (4) ANCHORS @ TOP USED FOR SETTING IN PLACE.
- SWL 10<sup>k</sup> @ 60° SLING (LH SE).
- HEAVIEST PICK, W04A.

$$\frac{24,700^{\#} \text{ PICK WT}}{4 \text{ LIFTERS}} = 6175^{\#} / \text{LIFTER}$$

$$\frac{10,000}{6175} = 1.62 > 1 \quad \underline{\underline{\text{OK}}}$$

#### CASE 4 RIGID FRAME (SETTING IN FIELD)

- (4) 2 1/2"  $\phi$  HOLES - CAST IN DECK.
- MUNCY TEACUP FITTING TC-32 WITH TC-32A 1" SLING AND NB-32 BUTTON.
- CONTROLLING CAPACITY IS 1" SLING - 19,000<sup>#</sup> W/ VERTICAL PICK



$$\begin{aligned} \text{SLING CAPACITY @ } 60^{\circ} &= 19^k \sin(60) \\ &= 16,450^{\#} \end{aligned}$$

- HEAVIEST PICK, RFBZ.

$$\frac{39,850^{\#}}{4 \text{ POINTS}} = 9960^{\#}$$

$$\frac{16,450^{\#}}{9960^{\#}} = 1.65 > 1 \quad \underline{\underline{\text{OK}}}$$