



- An efficient way to handle concrete pipes
- Light weight design
- Available with 7" and 12" diameter flanges.
- To be used with our special Muncy™ Machine NB Buttons

		A	B	C	D	Weight	
TC-24	3/4" - 7/8"	7.00	2.50	0.938	5.75	9.5 lbs	<u>NB-24, NB-28</u>
TC-32	1" - 1-1/8"	7.00	2.50	1.250	5.75	9.5 lbs	<u>NB-32, NB-36</u>
TC-40	1-1/4"	7.00	3.00	1.375	5.75	10 lbs	<u>NB-40</u>

		A	B	C	D	Weight	
TC-24A	3/4" - 7/8"	12.00	2.50	0.938	5.75	26 lbs	<u>NB-24, NB-28</u>
TC-32A	1" - 1-1/8"	12.00	2.50	1.250	5.75	26 lbs	<u>NB-32, NB-36</u>
TC-40A	1-1/4"	12.00	3.00	1.375	5.75	27 lbs	<u>NB-40</u>

RATED CAPACITY

~~TC-24 / TC-24A~~

~~3/4" - 10,864-LBS WLL~~

~~7/8" - 14,744-LBS WLL~~

TC-32 / TC-32A

1" - 19,012-LBS WLL

1-1/8" - 23,280-LBS WLL

~~TC-40 / TC-40A~~

~~1-1/4" - 29,100-LBS WLL~~