

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
FULL E & C	ROADWAY	EROSION CONTROL	CHANNEL	PIER	ABUTMENT NO. 1	ABUTMENT NO. 2	APPROACH SLAB NO. 1	APPROACH SLAB NO. 2	APPROACH SPAN	TRUSS	BRIDGE QUANTITY	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS		
	1												1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10					
	114												114		M	HEAVY DUTY STEEL BEAM GUARDRAIL	621.21					
	4												4		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53					
	4												4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60					
	100												100		M	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80					
	138												138		M	TEMPORARY TRAFFIC BARRIER	621.90					
	50												50		HR	FLAGGERS	630.15					
	1												1		LS	FIELD OFFICE-ENGINEERS	631.10					
	1												1		LS	TESTING EQUIPMENT - CONCRETE	631.16					
	1												1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17					
	1												1		LS	TESTING EQUIPMENT - PROTECTIVE COATINGS	631.18					
	1												1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25					
	1												1		LS	MOBILIZATION	635.10					
	1												1		LS	TRAFFIC CONTROL	641.10					
	356												356		M	DURABLE 100 mm YELLOW LINE	646.41					
	14												14		SM	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85					
			310										310		SM	GEOTEXTILE UNDER STONE FILL	649.31					
	160												160		SM	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41					
	150												150		SM	GEOTEXTILE FOR SILT FENCE	649.51					
	100												100		SM	GEOTEXTILE FOR FILTER CURTAIN	649.61					
	10												10		KG	SEED	651.15					
	5												5		KG	SEED-WINTER RYE	651.17					
	60												60		KG	FERTILIZER	651.18					
	1												1		T	AGRICULTURAL LIMESTONE	651.20					
	1												1		T	HAY MULCH	651.25					
	30												30		EACH	HAY BALES FOR EROSION CONTROL	651.26					
	70												70		CM	TOPSOIL	651.35					
			200										200		SM	GRUBBING MATERIAL	651.40					
	1												1		LS	EROSION AND SEDIMENT CONTROL PLAN	652.10					
	50												50		HR	MONITORING EROSION AND SEDIMENT CONTROL PLAN	652.20					
	1												1		LU	FIELD MAINTENANCE OF EROSION AND SEDIMENT CONTROL PLAN	652.30					
	1120												1120		SM	EROSION MATTING	654.10					
	7.1												7.1		SM	TRAFFIC SIGNS, TYPE A	675.20					
	212												212		M	FLANGED CHANNEL SIGN POST	675.301					
	2												2		EACH	REMOVING SIGNS	675.50					

PROJECT NAME: **BROOKLINE-NEWFANE**
 PROJECT NUMBER: **BHO 1442 (25)**
 FILE NAME: 195j2781Structures1j278qnt.xls
 PROJECT MANAGER: R. WHITCOMB
 DESIGNED BY: M. LOZIER
 QUANTITY SHEET #2
 PLOT DATE: 06/26/2003
 DRAWN BY: G. ROY
 CHECKED BY: M. LOZIER
 SHEET 6 OF 78