STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
10+083.8 RT	NARROW BRIDGE	1	750	750	0.563						1			X																			W5-2		E-154M
10+097.8 RT	STOP	1	750	750	0.563						1			X																			R1-1		E-143M
10+110.4 RT		1	750	750	0.563						1			X																			W1-1R		E-151M
	20 M.P.H.	1	600	600	0.360																											W13-1		E-155M
10+128.8 RT		1	300	900	0.270						1		X																			OBJECT MARKER		E-120M
10+129.3 LT		1	300	900	0.270						1		X																			OBJECT MARKER		E-120M
10+188.2 LT		1	300	900	0.270						1		X																			OBJECT MARKER		E-120M
10+190.7 RT		1	300	900	0.270						1		X																			OBJECT MARKER		E-120M
10+200.9 LT		1	1200	600	0.720						2		X																			W1-6		E-152M
												m	m 64.8	m 56.0	m	m	m	EA		kg	kg	kg		kg	kg	kg	kg								
	TOTALS				m^2 3.849	m^2	EA.	m^2				m 120.8			m					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BROOKLINE-NEWFANE
PROJECT NUMBER: BHO 1442 (25)

FILE NAME: 95j278\Structures\sj278tsl.i
PROJECT MANAGER: R. WHITCOMB
DESIGNED BY: G. ROY
PERMANENT TRAFFIC SIGNS SUMMARY SHEET (1)

PLOT DATE: 26-JUN-2003
DRAWN BY: G. ROY
CHECKED BY: M. LOZIER