

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
					700					700		LF	4 INCH WHITE LINE (FPQ)	646.20				
							260			260		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							135			135		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							50			50		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							5			5		LB	SEED	651.15				
							5			5		LB	SEED, WINTER RYE	651.17				
							15			15		LB	FERTILIZER	651.18				
							0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20				
							0.5			0.5		TON	HAY MULCH	651.25				
							70			70		CY	TOPSOIL	651.35				
							230			230		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN	652.10				
							50			50		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							90			90		SY	TEMPORARY EROSION MATTING	653.20				
							10			10		CY	TEMPORARY STONE CHECK DAM, TYPE II	653.26				
							30			30		CY	VEHICLE TRACKING PAD	653.35				
							10			10		EACH	FILTER BAG	653.45				
							500			500		LF	PROJECT DEMARCATION FENCE	653.55				
					0.66					0.66		SF	TRAFFIC SIGNS, TYPE A	675.20				
					20					20		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
					6					6		EACH	REMOVING SIGNS	675.50				
							110			110		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT)(FPQ)	900.608				
							36600			36600		LB	SPECIAL PROVISION (STRUCTURAL STEEL, CURVED PLATE GIRDER, GRADE HPS 70W)(FPQ)	900.635				
							10			10		LF	SPECIAL PROVISION (BRIDGE FIBERGLASS DRAIN SYSTEM)	900.640				
							280			280		LF	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED HDSB/FASCIA MOUNTED/STEEL TUBING)(FPQ)	900.640				
					1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL INCLUSIVE)	900.645				
					1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
					1					1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
					145					145		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: SPRINGFIELD
PROJECT NUMBER: BRO 1442(26)

FILE NAME: s95j282qs.xls
PROJECT LEADER: K. HIGGINS
DESIGNED BY: J. LACROIX
QUANTITY SHEET - 2

PLOT DATE: 30-AUG-2011
DRAWN BY: R. PELLETT
CHECKED BY: J. LACROIX
SHEET 5 OF 52